

EDGEWATER Community Hub

Pre-Development Planning



21 February 2024

Prepared by:

HAWORTH | Development
Consulting

PO Box 223, Invermere, BC V0A 1K0

T: 250-342-1227

E: richard@haworthconsulting.ca

Table of Contents

1. Introduction

1.1 Background and Purpose.....

1.2 Objectives of the Redevelopment

1.3 Scope of the Document.....

2. Public and Community Engagement

2.1 2010 Public and Community Engagement.....

2.2 2021 Public and Community Engagement.....

2.3 2022 Community Update.....

2.4 2024 Public and Community Engagement

3. Site Analysis

3.1 Site Location and Description.....

3.1.1 Vermillion Property

3.1.2 Post Office Property

3.2 Current Property Assessment.....

3.2.1 Vermillion Property

3.2.2 Post Office Property

3.3 Environmental Assessment

3.3.1 Vermillion Property

3.3.2 Post Office Property

3.4 Infrastructure Evaluation

3.5 Geotechnical Assessment.....

3.6 Zoning and Land Use.....

3.6.1 Vermillion Property

3.6.2 Post Office Property

4. Development Program and Conceptual Design

4.1 Development Program

4.1.1 Vermillion Property

4.1.2 Post Office Property

4.2 Consideration for BC Housing

4.3 Building Form and Architectural Concepts.....

4.3.1 Vermillion Property

4.3.2 Post Office Property

- 4.4 Site Planning..... 39
 - 4.4.1 Vermillion Property 39
 - 4.4.2 Post Office Property 42
- 4.5 Development Phasing..... 44
- 4.6 Universal Design and Accessibility..... 46
- 4.7 Energy Efficiency and Sustainability Considerations 46
- 4.8 Safety and Accessibility 46
- 5. Preliminary Budget**
 - 5.1 Preliminary Project Budget 47
 - 5.1.1 Vermillion Property 47
 - 5.1.2 Post Office Property 49
- 6. Regulatory Approvals**
 - 6.1 Land Use Approvals 53
 - 6.1.1 Vermillion Property 53
 - 6.1.2 Post Office Property 53
 - 6.2 Subdivision 55
 - 6.2.1 Vermillion Property 55
 - 6.2.2 Post Office Property 55
 - 6.3 Environmental Clearance 55
 - 6.4 Geotechnical Assessment 55
- 7. Next Steps**
 - 8.1 Next Steps 56
 - 8.1.1 Vermillion Property 56
 - 8.1.2 Post Office Property 56

Appendices

Appendix A	Working Towards a Sustainable Economy in Edgewater, Community Engagement Report, Feasibility Study for Community Hub Report, Centre for Innovative and Entrepreneurial Leadership, November 2010
Appendix B	Edgewater Redevelopment Planning Committee, Community Update, March 2022
Appendix C	Edgewater Open House – Presentation Panels, February 2024
Appendix D	Edgewater Open House – Comments Summary, February 2024
Appendix E	RDEK Upper Columbia Valley Zoning Bylaw
Appendix F	Columbia Valley Child Care Snapshot, City Spaces Consulting, November 2022
Appendix G	Site Plan – Vermillion Property – Option 1 & 2
Appendix H	Site Plan – Post Office Property

The Edgewater Community Hub is an initiative of the



with funding from



1.0 Introduction

1.1 Background and Purpose

Haworth Development Consulting Ltd. was engaged by the Edgewater Redevelopment Planning Committee through the Regional District of East Kootenay, with financial support from Columbia Basin Trust, to prepare a redevelopment plan for lands in the core area of Edgewater owned by the Regional District of East Kootenay and known as the **Edgewater Community Hub**.

1.2 Objectives of the Redevelopment

The objectives of this redevelopment plan are:

- Economic Vitality – to stimulate local economic activity by providing commercial space that accommodates a local Canada Post outlet and additional commercial / retail opportunities as may become viable in the future with the goal of providing services to residents in the local community.
- Community Enhancement – to create a welcoming and inclusive space that enhances community interaction and offers amenities and while tying into and supporting the neighbouring community greenspace and community hall.
- Sustainability – to implement sustainable design and construction practices reducing the environmental footprint and operating costs of the development in accordance with the Regional District's requirements for energy efficiency.
- Mixed-Use Integration – To integrate commercial and residential uses, promoting a live – work – play environment while providing some attainable housing to residents of the community.

1.3 Scope of this Document

This document is intended to provide an overview of the Community Hub Redevelopment project and act as a resource as the project moves forward to implementation. Key areas of the document are:

- Public and community engagement
- Site analysis
- Development program and conceptual design
- Preliminary budget considerations
- Regulatory approvals
- Next steps

2.0 Public and Community Engagement

2.1 2010 Public and Community Engagement

The Regional District of East Kootenay (RDEK) has completed significant consultation with various stakeholders regarding potential uses of the subject properties. The consultation commenced in 2010 when the RDEK engaged the Centre for Innovative and Entrepreneurial Leadership (CIEL) to facilitate community engagement. CIEL summarized the process at that time as follows:

RDEK Director Gerry Wilkie and several citizens of Edgewater initiated a project in the spring of 2010 to determine the feasibility of replacing the community's deteriorating post office building with a vital community "hub", housing the post office and several other needed community services and/or businesses. It was believed that the building of a hub might also act as a catalyst for establishment of other businesses on available commercial land in this core area.

Edgewater had experienced the loss of Kootenay Savings Credit Union (KSCU) branch to Radium and it was believed that the loss of the post office would be detrimental to the future of the community. Use of the former KSCU building (which had been vacant since it was donated to the community in 2009 and adjacent to the post office building) was also to be factored into the community "hub" plan. Currently, the community has only one storefront business - a general store.

CIEL (Centre for Innovative & Entrepreneurial Leadership), mainly through Executive Director Mike Stolte, was contracted to undertake a community engagement process - public meetings, a survey, and key stakeholder interviews - to determine community needs in the broader context of creating a healthy economy for Edgewater.

Working with a community advisory committee (AC) ... to use the findings to determine acceptable and possible hub uses and determine whether the replacement of the building was feasible given the probable rents that could be generated. Further, through the engagement process CIEL was to identify initiatives that could be used to generate a healthy and sustainable economy in Edgewater.

The community engagement completed by CIEL included:

- Community Engagement Session Public Meeting – June 22, 2010
- Edgewater Community Vision & Economic Revitalization Survey – July 2010
- Community Engagement Session Public Meeting – October 13, 2010

The conclusion of the community engagement and survey were presented by CIEL at the October 13, 2010 meeting and in the summary report prepared by CIEL.

At the Oct. 13/10 Advisory Committee meeting and the Community Session (immediately following the AC meeting) Mike laid out the next steps to complete the project. Next steps on the hub were identified to be:

1. *Determine ownership. (There was support for a community organization managing an RDEK-owned facility. Attendees expressed clearly that any hub must break-even at minimum and not impose additional taxes on residents).*

2. *Identify possible anchor tenants. (Determined through a synthesis of inputs from community engagement process. The intent of the process was to identify possible businesses and services that might be tenants in a community hub & determine whether rents generated from these might be sufficient to offset costs - mortgage, operating expenses, etc.)*
3. *Outline space requirements and possible design configurations (see below)*
4. *Cost estimates on building construction (see below)*

Mike [CEIL] presented those ideas which seemed to have the most community support (determined from the various community engagement mechanisms [key stakeholder interviews, survey, community meeting]) to the Advisory Committee and to the public at the Community Session II (October 13, 2010). Some of these were community services that did not seem likely to generate an income (to offset rent/mortgage payments) or generate marginal income. Others, indicated below (see - \$ generating), were seen to have the potential to generate some income.

- *Coffee shop/bakery (\$ generating)*
- *Display windows of local businesses (\$ generating)*
- *Business centre/ directory/photocopier/ trades listing (\$ generating)*
- *ATM*
- *Tourism centre (with maps, some local history, trailhead, info on local outfitters- possibly volunteered staffing)*
- *Day care/ mom & tots space*
- *Pharmacy/medical (one day/week)*
- *Library/book exchange*
- *Other**

After these hub ideas were presented, the community was asked for feedback.

Both the AC [Advisory Committee] and the attendees at the public meeting generally agreed with possible uses and assumptions of space allocations. The feedback was incorporated into the feasibility plans going forward.

** The idea of incorporating affordable housing units above the commercial hub was discussed at the AC. It was thought that somewhere between 2 units (approximately 1700 s.f. each) to 4 units (800-900 s.f. each) could be built at a lower cost than construction costs for ground floor units. There was also discussion involving the possibility of the Columbia Basin Trust or other provincial agencies offsetting costs of these units.*

A copy of the CIEL report "Working Towards a Sustainable Economy in Edgewater, Community Engagement report, Feasibility Study for Community Hub Report, November 2010" is attached as Appendix A.

2.2 2021 Public and Community Engagement

In October 2021, RDEK Area 'G' Director Gerry Wilkie held a community meeting attended by about 50 residents at the Community Centre. These residents voiced their ideas, concerns, and questions about redevelopment of the post office property. As a result of this meeting, a small group of residents volunteered to form the **Edgewater Redevelopment Planning Committee**.

2.3 2022 Community Update

In March 2022 the Edgewater Redevelopment Planning Committee issued a Community Update.

The update noted that the Edgewater Redevelopment Planning Committee had been joined by Gerri Brightwell, Manager with BC's Regional Economic Development Branch for our region, and committee also enjoyed hands-on support from the Columbia Valley Chamber of Commerce.


The update stated that the committee has been meeting monthly and is looking into the opportunities and implications of several possible concepts for the subject properties with a focus on practical solutions, including funding opportunities, partnership options and ways of implementing and managing projects in communities like Edgewater.

The update indicated that the options being reviewing range from trying to maintain the status quo with small scale changes, to more comprehensive options possibly involving commercial or other partners.

The committee's goal going forward was to:

- answer questions the community posed at past meetings and since; and,
- to reach a point where we can invite the community to share what we have learned and to present some options for the future of the properties in the centre of Edgewater.

A copy of the 2022 Community Update is attached as Appendix B.



2.4 2024 Public and Community Engagement

The Edgewater Redevelopment Planning Committee, in cooperation with the Regional District of East Kootenay, engaged with the Edgewater community to present the development concepts contained in this report.

A community open house was held on February 6, 2024 at the Edgewater Community Hall. Approximately 100 people attended the open house to view the presentation and ask questions about the proposed direction forward (77 people provided their information on the sign-in sheet. The figure of 100 is based on our observance of the number of couples that attended with only one person signing in and the number of people that did not sign-in).

The open house included a series of 17 panels (copies of the panels are provided in Appendix C):

- Welcome
- Objectives of the Development Plan
- Development Properties
- Development Program
- Building Form and Character – Character imagery
- Building Form and Character – Vermillion Property
- Building Form and Character – Post Office Property
- Site Plan – Vermillion Property – Option 1
- Site Plan – Vermillion Property – Option 2
- Site Plan – Post Office Property
- Construction Budget – Vermillion Property
- Construction Budget – Post Office Property
- Development Phasing – Post Office Property
- Construction Budget – Post Office Property, Post Office Only
- Frequently Asked Questions – Canada Post, Child Care Facility, Attainable Housing Units
- Frequently Asked Questions – Funding
- Frequently Asked Questions – Ownership and Operation
- / Next Steps



Guests were welcomed when they arrived and provided with a brief overview of the format of the presentation and then asked to fill out a comment sheet when they had reviewed the panels. Members of the Edgewater Redevelopment Planning Committee were available to answer questions from attendees.

A total of 32 comment sheets were completed by attendees (see Appendix D). A further three attendees provided comments by email after the open house.

The comment sheets indicate community support for the proposed child care facility and post office property redevelopment. Themes within the comments included:

- Desire to see a new post office facility sooner than other aspects of the plan. Generally appears to be strong desire for this use to be provided first. Potential concept to move new post office to the Vermillion property and the child care facility to the current post office property.
- Mixed responses about need for child care facility – some question need while other see the need.
- Concern about impact on property taxes resulting from proposed development. Requesting clarity on financial implications for residents before this proceeds too much farther.
- General consensus that the proposed look of buildings fits within the vernacular of Edgewater and is the direction the community would like to see.
- Misunderstanding that attainable housing does not mean “low-income” and perceived issues around low-income housing. Concern that housing could be used as support for substance abuse rehabilitation, etc.
- Concern about management of attainable housing units.

The Next Steps recommended in this report (see Section 7) are based on the positive feedback from the Edgewater community.

3.0 Site Analysis

3.1 Site Location and Description

The project includes two distinct development areas: the current post office property at the intersection of Selkirk Avenue and Sinclair Street and a vacant property at the corner of Selkirk Avenue and Vermillion Street.

All the subject properties are owned by the Regional District of East Kootenay. Figure 1 illustrates the location of the Vermillion property and Post Office property in Edgewater.



Figure 1 – Property Location

3.1.1 Vermillion Property

The Vermillion property located at the intersection of Selkirk Avenue and Vermillion Street comprises three parcels of land legally described as follows and as shown in Figure 2, Vermillion Property – *Existing Conditions / Air Photo*:

- Lot 15, Block 7 District Lot 353 Kootenay District Plan 1185
PID: 017-218-462
- Lot 16, Block 7 District Lot 353 Kootenay District Plan 1185
PID: 017-218-471
- Lot 17, Block 7 District Lot 353 Kootenay District Plan 1185
PID: 017-218-489

These lots together create a parcel measuring 22.9m (75 ft) frontage with a depth of 36.6m (120 ft) and a total area of 836.1m² (9,000 ft²) or approximately 0.21 acre.

3.1.2 Post Office Property

The Post Office property located at the intersection of Selkirk Avenue and Sinclair Street comprises seven parcels of land legally described as follows and as shown in *Figure 3, Post Office Property – Existing Conditions / Air Photo*:

- *That Part of Lot 15, Block 2 District Lot 353 Kootenay District Plan 1185, Lying Southwest of a Line Parallel to and 28 Feet Distant from the Southwesterly Boundary of the said Lot.*
PID: 015-805-633
- *That Part of Lot 16, Block 2 District Lot 353 Kootenay District Plan 1185, Lying Southwest of a Line Parallel to and 28 Feet Distant from the Southwesterly Boundary of the said Lot.*
PID: 015-805-641
- *That Part of Lot 17, Block 2 District Lot 353 Kootenay District Plan 1185, Lying Southwest of a Line Parallel to and 28 Feet Distant from the Southwesterly Boundary of the said Lot.*
PID: 015-805-650
- *Lot 14, Block 2, District Lot 353 Kootenay District Plan 1185.*
PID: 015-815-510
- *Lot 15, Block 2 District Lot 353 Kootenay District Plan 1185, Except That Part Lying Southwest of a Line Parallel to and 28 Feet Distant from the Southwesterly Boundary of the said Lot.*
PID: 015-815-595
- *Lot 16, Block 2 District Lot 353 Kootenay District Plan 1185, Except That Part Lying Southwest of a Line Parallel to and 28 Feet Distant from the Southwesterly Boundary of the said Lot.*
PID: 015-815-609
- *Lot 17, Block 2 District Lot 353 Kootenay District Plan 1185, Except That Part Lying Southwest of a Line Parallel to and 28 Feet Distant from the Southwesterly Boundary of the said Lot.*
PID: 015-815-617

These lots together create a parcel measuring 32.8m (107.5 ft) frontage with a depth of 36.6m (120 ft) and a total area of 1198.4m² (12,900 ft²) or approximately 0.30 acre.

The lands west of the Post Office property area also owned by the RDEK and comprise a park and the Edgewater Community Hall. The Edgewater Community Hall is approximately 167 m² (1,800ft²) of open hall space plus a stage and includes a kitchen, washrooms, main entry and covered deck. Total capacity is 200 people, seating 170 comfortably.




Figure 2 - Vermillion Property – Existing Conditions / Air Photo




Figure 3 - Post Office Property – Existing Conditions / Air Photo

3.2 Current Property Assessment

3.2.1 Vermillion Property

The Vermillion property is vacant with no existing buildings or structures. See Figures 7 and 8 illustrating the property.

3.2.2 Post Office Property

The Post Office property includes two existing buildings. The post office building and the old credit union building.

The post office building includes space for the post office, public library and a garage. The public library and garage spaces are not currently being used.

The post office operates in a portion of the building but is too small for continued functional use. Currently, the post office occupies a space of approximately 79m² (850 ft²) which includes the original post office space, the recent expansion and the shared bathroom.

A structural assessment of the building was completed in 2022 which determined that while the post office portion of the building is safe for its current use, continued long-term use of this building is not recommended due to the various structural issues identified. As a result, this building should be demolished when redevelopment of the property commences. Figure 4 and 5 illustrates the current condition of the exterior of the post office building.

The old credit union building is not in use and has been deemed unusable due to structural concerns. This building will be demolished when redevelopment of the property commences Figure 6 illustrates the current condition of the exterior of the credit union building.



Figure 4 –
Current
condition of
exterior of Post
Office building



*Figure 5 -
Current
condition of
exterior of
Post Office
building*



*Figure 6 -
Current
condition of
exterior of old
credit union
building.*



*Figure 7 -
Current
condition of
Vermillion
property
(south
portion)*



*Figure 8 -
Current
condition of
Vermillion
property
(north
portion)*

3.3 Environmental Assessment

A Phase 1 Environmental Assessment of the properties has not been completed.

3.3.1 Vermillion Property

From discussions with members of the Edgewater Redevelopment Planning Committee, it is understood that the Vermillion property has never been used for any commercial or industrial purpose. The property has been previously utilized for residential purposes as a 'teacherage' providing accommodation for teachers at the local school.

There are no known Schedule 2 activities that have occurred on the property, nor is there reason to believe that any Schedule 2 activities that may have occurred on neighbouring properties may have impacted the subject property.

3.3.2 Post Office Property

The Post Office property has been utilized as a credit union, post office, library and other similar institutional and retail uses. The current post office building was originally constructed in 1950 for the Edgewater Improvement District office and post office. Parts of the building have also been used as a library. The improvement district office included a single garage used for parking an improvement district vehicle. The garage was not utilized for vehicle maintenance.

The currently vacant building on the south portion of the property was owned and operated by the Edgewater & District Credit Union until 2009 when, after merging with Kootenay Savings Credit Union some years earlier, a new branch was constructed in Radium Hot Springs.

There are no known Schedule 2 activities that have occurred on the property, nor is there reason to believe that any Schedule 2 activities that may have occurred on neighbouring properties may have impacted the subject property.

An old septic system may remain on the Post Office property that must be properly decommissioned. A septic system is not considered a Schedule 2 activity and will not impact redevelopment of the property.

3.4 Infrastructure Evaluation

The RDEK provide water and sewer in the Edgewater community through the Edgewater Water System and the Edgewater Sewer System. Suitable capacity exists within both the water and sewer systems for development proposed on the subject properties.

All new development must connect to these water and sewer systems and pay applicable connection fees and usage fees. Further detail about these systems and costs for service are available on the RDEK website: <https://www.rdek.bc.ca/departments/engineering/>

3.5 Geotechnical Assessment

The structural assessment of the post office building was completed in 2022 by Columbia Valley Engineering. During this assessment it was noted that the west side of the post office building is settling. Columbia Valley Engineering found:

“The external ground in this area has sunk appreciably, over a width of approximately 25’. This settlement has caused the footings under the children’s room of the library and the ground slab of the garage to move vertically 1-3” downwards, which in turn as caused the party wall to rack, opening up a 3/4” crack at the top of the wall. The roof is sagging at this point, as the support below has dropped.

At this time, the cause of the settlement is unknown and would require a geotechnical investigation to confirm the exact cause. The water found in the sump under the building may be contributing to the issue. This would be confirmed by the geotechnical investigation.”

As noted by Columbia Valley Engineering, a geotechnical assessment of the property should be undertaken to confirm the cause of any settlement and to ensure that this issue does not impact any future development of the property.

3.6 Zoning and Land Use

3.6.1 Vermillion Property

The RDEK Upper Columbia Valley Zoning Bylaw currently designates the Vermillion property as Single Family Residential (R-1 Zone). This zone permits development of single-family dwellings with the following ancillary uses permitted: home based business, auxiliary dwelling unit, boat and recreational vehicle storage, and uses, buildings and structures accessory to a permitted use.

The Steamboat - Jubilee Mountain Official Community Plan, Bylaw 3022, 2021 designates the Vermillion property as Low Density Residential (R-SF). This land use supports single family and multi-family residential development.

Rezoning of the Post Office property will be required to facilitate development as envisioned by the community. An OCP amendment will also be required for the Vermillion property.

3.6.2 Post Office Property

The RDEK Upper Columbia Valley Zoning Bylaw No.3255, 1992 currently designates the Post Office property as Community Commercial Zone (C-1 Zone). This zone permits a range of retail, business and professional office, commercial accommodation (ie. hotel), and food service uses (see Appendix E – RDEK Upper Columbia Valley Zoning Bylaw).

The Steamboat - Jubilee Mountain Official Community Plan, Bylaw 3022, 2021 designates the Post Office property as Commercial (C). This land use supports the limited range of local, service and commercial land uses as identified in the zoning bylaw.

The OCP also establishes policies for commercial land use in the plan area. The following policies are applicable to the subject properties:

- (a) The revitalization of the Regional District owned commercial buildings is supported. In order to facilitate the process, the creation of a community group dedicated to advancing the revitalization is encouraged. Regional District participation in the revitalization process is supported subject to the allocation of available resources, funding and staff capacity.*
- (b) The rezoning of Lots 15-17 Block 7 Plan NEP1185 District Lot 353, Kootenay District to a commercial use is supported.*

Rezoning of the Post Office property will be required to facilitate development as envisioned by the community. An OCP amendment will also be required for the Vermillion property.

The requirements for rezoning and OCP amendment are discussed later in this report.

4.0 Development Program and Conceptual Design

4.1 Development Program

The development program for the properties has been established based on the findings of the 2010 CEIL report “*Working Towards a Sustainable Economy in Edgewater, Community Engagement report, Feasibility Study for Community Hub Report*” and direction from the Edgewater Redevelopment Planning Committee.

4.1.1 Vermillion Property

The Vermillion property is proposed for development of a daycare facility. The daycare proposed is envisioned for approximately 30 children.

The Eva Joseph Learning and Cultural Society and Little Badgers Early Learning Centre, with funding from the Columbia Basin Trust, commissioned a study to provide a snapshot of the current state of child care for the Columbia Valley region. The study, “Columbia Valley Child Care Snapshot” concluded:

There is presently only a 19% child care coverage rate observed in the Columbia Valley – categorizing the community as a child care desert. It is recommended to consider increasing the coverage rate in the community to 80% for ages 0 to 3 years, 70% for ages 3 to 5 years, and 55% for ages 6 to 12 to adequately service the community’s child care needs. In order to meet these targets, an increase of 606 child care spaces (for a total of 857 licensed spaces) is needed – an additional 138 spaces for under age 3 years, 118 spaces for ages 3 to 5 years and 350 spaces for ages 6 to 12 years.

As the population is not projected to increase over the next 10 years, it is not anticipated that the targets will increase significantly at this time. However, the targets should be re-evaluated as the community changes. It would be beneficial to engage with families to discover some of the nuances that families experience when accessing child care in the community. As part of future strategies to address the need for more child care, it will be imperative to consider ways to create inclusive child care that can meet the diverse needs of the local population. Future considerations such as language, culture, and creating flexible options that can accommodate families with varying needs (e.g. parents with schedules that do not align with a typical 9 – 5 work day, lone parent families that may be working more than one job, etc.) should be explored in further detail when creating more child care spaces in the community.

The Columbia Valley Child Care Snapshot is attached as Appendix F.

The Province of BC and UBCM publish a guide titled “*Stepping Stones, Child Care Planning Guides For BC’s Local Governments*”. This guide summarizes the requirements of the *Child Care Licensing Regulation* which regulates child care facilities in British Columbia.

The Stepping Stones guide includes the following guidelines for development of a child care facility:

Selecting a Location: The best site for a child care centre is near to, or co-located on the grounds of other public community spaces such as schools, community centres and parks, and therefore offer a continuum of services for multiple age groups. This allows for coordinated services that enhance

program quality, as well as construction and operating cost efficiencies gained by building facilities that can share spaces.

Site and Facility Considerations - Adjacent Uses: Child care facilities should be located in proximity to compatible, safe and environmentally appropriate land uses. This provides easy access, seamless services for children, convenience for busy families, builds on existing local infrastructure, and offers efficient ways to share resources and assets. It also offers opportunities for service providers to plan together, integrate services and to provide a full range of other important supports to children and their parents/guardians.

Site and Facility Considerations - Relationship to Grade: Child care facilities should be designed to provide barrier-free, same level access from the exterior to the interior of a building (i.e., wheelchair, mobility aid accessible). This makes the space more accessible and inclusive for small children, families and people with physical support needs.

Site and Facility Considerations - Relationship of indoor and outdoor spaces: Outdoor space should be at the same level as the indoor space wherever possible and contiguous with it in order to make the space easily accessible to children and their caregivers. When possible, the two areas should be planned together and ramps for wheeled equipment should be provided when a level change exists. A strong visual and physical connection should exist between the indoor and outdoor activity area to allow children and staff to flow freely between inside and outside.

Site and Facility Considerations - Environmental Considerations: The availability of natural light is important for a healthy environment. Care should be taken to install window coverings to create a cooling affect during the summer months and additional insulation during the winter months. It is recommended that child care areas have their own systems for heating, ventilation, and air cooling to allow staff to regulate the temperature according to the children's needs. Ventilation should be planned for children's washrooms, diaper areas, sleep areas and kitchens to reduce exposure to air borne illness and diseases.

Site and Facility Considerations - Safety and Security: Pedestrian access should be safe, well-lit and allow for strollers and bikes to be safely wheeled, ideally visible to many people. To ensure close monitoring, entrances and exits must be controlled. The outdoor space must be enclosed in a manner that is suitable for the ages of the children with non-climbable fences.

Site and Facility Considerations - Parking, Pick Up and Drop Off: Accessing the child care needs to be carefully considered both from an access and a safety perspective.

Interior and Exterior Design: The physical environment has a significant impact on the children, the staff, parents/guardians and the broader community. The location, the type and amount of space, how the space is organized, the type and arrangement of furnishings and equipment, availability of natural light and views to the outdoors, health and safety considerations, the amount and layout of outdoor space and proximity to indoor, colours, surfaces and textures are all important aspects of designing and building child care.

Interior: The Provincial Child Care Licensing Regulation require 3.7 metres squared of useable floor area per child and have requirements for maximum group sizes. These minimums are for spaces that are used for activities only and do not include storage, washrooms, nap rooms, staff rooms, offices, kitchens, hallways, cloakrooms, and janitorial closets. In addition, consideration in design must be given to allow for building inefficiencies, circulation and services.

Large, open designs are preferred with an emphasis on flexibility to accommodate the diverse, developmental abilities of children and to be responsive to emerging community needs. All play areas (inside and out) should be accessible to all children, safely constructed, free from hazards and in good repair. Equipment, furniture and play materials must be suitable for the age and developmental levels of the children and accessible for children with diverse support needs.

Exterior: BC's Child Care Licensing Regulation requires a minimum of 6 metres square per child of outdoor play space. This is less than half the size of a standard parking space for a car. This open space is reduced even further once landscape elements, play structures and walkways are installed. Outdoor play areas must be accessible for children with diverse needs (i.e. mobility needs).

Empirical research indicates children benefit from more outdoor spaces than the current minimum standards in the provincial Child Care Licensing Regulation. For example, a 1999 Canada wide safety assessment of outdoor play spaces in child care centres recommended 13.5 metres square outdoor space per child in order to provide children "with the diversity of experiences needed outside for their development while respecting safety standards." Other studies recommend between 7 and 25 metres square per child. In addition to the amount of space, the nature and organization of the space is also important. Every effort should be made to link outdoor play space with the inside play space. Centres that had direct physical and visual connection to their outdoor play space from inside, use the outdoors more frequently than those centres that lack this connection.

Additional Considerations if Local Government will be the Owner of the Spaces: Local governments have an important regulatory role for child care development in their communities, which includes zoning approvals, building inspections, and business licensing. And in BC, local governments may be owners, landlords, and operators of licensed child care spaces and play critical leadership roles in planning and facilitating new child care developments.

If Local Government will be the Owner – Landlord: The local government may be the owner/ builder of child care, and the landlord of spaces negotiated as part of new developments or publicly owned assets like a community centre. As an owner-landlord, it is in the best interest of the local government to:

- a. Build spaces that are financially sustainable, ideally with multiple programs and co-located with other public services that meet the highest needs in the community.
- b. Build quality spaces to ensure long-term durability in the most accessible and safe locations possible. Child care facilities have daily, year-round high usage. In order to ensure safe, high-quality infrastructures for many years and multiple generations of children, investing more capital resources up front to construct spaces that can withstand this intense use which can result in a longer lifespan with fewer renovation expenses over time.
- c. Select an architect and/ or designer who has experience with designing licensed child care and involve an experienced child care operator early on in the design process to ensure a quality environment.
- d. Involve local officials early to ensure that the facility meets all necessary requirements.

If Local Government will be the Owner – Operator: The local government entity may choose to directly operate the child care spaces. It is then recommended that:

- a. Time is spent to fully understand the legislation and regulation governing child care (*BC Child Care Rules and Regulations*).
- b. Internally, work is completed to assess financial and operational impacts to ensure long-term sustainability. (For example, human resource requirements including collective agreements, administration and infrastructure requirements for items like fee collection and reporting to the Province.)
- c. Consider items above under Owner – Landlord.
- d. Identify and secure a subject matter expert (either a lead staff person internally or secure external support) to manage and provide oversight to the licensed child care.

Table 4.1 outlines the requirements for group sizes for a Licensed Child Care facility. Licensed child care facilities are monitored and regularly inspected by regional health authorities. They must meet specific Requirements for health and safety, staffing qualifications, record keeping, space and equipment, child-to-staff ratios, and programming.

Table 4.1 - Requirements for Group Sizes for a Licensed Child Care Facility

Child Care Type	Ages	Maximum Group Size
Group child care Under 3 years	From birth to 36 months	12 children
Group child care 2.5 years old to school age	From 30 months to school age (Kindergarten)	25 children
Group child care School age (before and after school care)	School age (Kindergarten and up)	24 children from Kindergarten and Grade 1 or 30 children from Grade 2 and older with no Kindergarten or Grade 1 children present
Multi-age child care	From birth to 12 years old	8 children, having no more than 3 children younger than 36 months old and, of those 3, no more than one child younger than 12 months old or having no more than 3 children younger than 36 months old
Preschool 2.5 years old to school age	From 30 months to school age (Kindergarten)	20 children
Occasional child care	18 months old and up	16 children if children under 36 months are present or 20 children if children under 36 months are not present

The RDEK Zoning Bylaw also established requirements for a child care facility. Zoning Bylaw 3255 defines Group Day Care as a facility for the temporary care of children licensed as Group Child Care (various ages) or Multi-age Child Care under the Community Care and Assisted Living Act and the Child Care Licensing Regulation. Group Day Care uses are only permitted in the Public Institutional (P-1) Zone.

Within the P-1 Zone the following restrictions apply:

Siting

- (a) No person shall site a principal building in the P-1 zone which has:
 - (i) a front yard less than 7.5 m (24.6 ft)
 - (ii) a rear yard less than 4.5 m (14.8 ft)
 - (iii) a side yard less than 4.5 m (14.8 ft)

Size and Dimensions of Buildings and Structures

- (a) No person shall site a principal building or structure in the P-1 zone which exceeds a height of 12.0 m (39.4 ft).
- (b) No person shall site an accessory building or structure in the P-1 zone which exceeds a height of 5.0 m (16.4 ft).

The RDEK Zoning Bylaw also establishes parking and loading requirements for all uses. The following are required for a day care facility:

Parking

Daycare, preschools and elementary schools	1 per 50m ² (538.2 ft ²) of gross floor area
--	---

Loading

Offices, assembly use and institutional and public uses	1 per 3000m ² (32293 ft ²) of gross floor area
---	---

All required parking and loading spaces must be provided on the parcel being served. Parking is not permitted within the road right-of-way unless permitted by MOTI and a development variance permit has been issued by the RDEK permitting the parking stalls to not be on the property.

The RDEK Zoning Bylaw requires parking stalls to be no less than 2.7m wide by 6.0m deep. A loading bay is required to be no less than 3.5m in width and 9.0m in length.

Based on the above requirements for a child care facility and our understanding of the need in the community, a facility for 30 children is proposed. For planning purposes, the following assumptions have been made:

Table 4.2 – Proposed Capacity for Child Care Facility

Child Care Type	Ages	Proposed Maximum Capacity
Group child care Under 3 years	From birth to 36 months	Not more than 8 children
Group child care 2.5 years old to school age	From 30 months to school age (Kindergarten)	Not more than 12 children
Group child care School age (before and after school care)	School age (Kindergarten and up)	Not more than 10 children from Kindergarten and older
TOTAL CAPACITY		Not more than 30 children

Based on the **proposed capacity of 30 children** the facility will require not less than 111m² (1,195 ft²) of indoor space useable floor area (30 children x 3.7m² / child). In addition to the usable floor space, allowance must be made for storage, washrooms, nap rooms, staff rooms, offices, kitchens, hallways, cloakrooms, and janitorial closets, building inefficiencies, circulation, and services. Assuming approximately 50% efficiency of the usable floor area, a total floor area of 222m² (2,390 ft²) is required.

In addition to the indoor space, the facility will require not less than 180m² (1,938 ft²) of outdoor space (30 children x 6.0m² / child) plus allocation for parking, sidewalks, non-accessible space (ie. mechanical area), and other considerations. Additional outdoor space will be provided as possible on the property.

Based on the above building size, a total of three parking spaces are required (1 space per 1 per 50m² of gross floor area) and one loading space is required. The minimum required parking would not be sufficient to allow for multiple parents to be dropping off children and still allow for suitable parking for staff of the facility. Additional parking spaces will be provided as possible. Additionally, a lay-by would be beneficial for dropping off children. As a lay-by would be located within the road ROW, it must be permitted by the Ministry of Transportation and Infrastructure (MOTI).

In accordance with the requirements of the P-1 zone, all proposed buildings and structures must meet required setbacks. As noted above, the minimum required front yard setback is 7.5m while the minimum required rear and side setbacks are 4.5m. These setbacks reduce the usable area of the Vermillion property from the total parcel area of 836.1m² (9,000 ft²) to a usable parcel area of 340.6m² (3,666 ft²).

4.1.2 Post Office Property

The Post Office property is proposed for development of a range of uses that may include a new post office, public gathering spaces (outdoor) and attainable non-market rental units.

Post Office

The Edgewater community post office is considered a critical component and keystone of the redevelopment plan for the Post Office property. The post office has served the Edgewater community for years and its loss would be felt by all residents in the community.

As noted previously, the current post office occupies a space of approximately 79m² (850 ft²) which includes the original post office space, the recent expansion and the shared bathroom. According to the current operator, this space is not suitable for continued operation.

The post office operator proposes a new space of not less than 80m² (850 ft²) but would prefer 110m² (1200 ft²). The smaller space would serve the existing residents from Radium Hot Springs to Spur Valley but would not allow for new residents nor would it be sufficient for the increasing growth in parcel shipment (ie. Amazon, etc).

The RDEK Zoning Bylaw establishes requirements for government services (which would include a post office). Zoning Bylaw 3255 defines Government Services as local, provincial or other government services including office uses for the purpose of local or other government administration. Government Services uses are permitted in the following zones:

- Resort Core Zone (RES-4)
- Community Commercial Zone (C-1)
- Service Commercial Zone (C-2)
- Light Industrial Zone (I-1)
- Public Institutional Zone (P-1)
- Public Parks and Open Space Zone (P-2)
- Public Works and Utility Zone (P-3)

The RDEK Zoning Bylaw also establishes parking and loading requirements for all uses. The following are required for government services:

Parking

Government Services 1 per 35m² (376.7 ft²) of gross floor area

Loading

Offices, assembly use and institutional and public uses	1 per 3000m ² (32293 ft ²) of gross floor area
---	---

Based on the above building size, a total of four (4) parking spaces are required (1 space per 35m² of gross floor area) and one loading space is required. Additional parking may be provided as space permits, or a lay-by could be provided for quick stops at the post office (such as to check a mailbox or drop of mail).

All required parking and loading spaces must be provided on the parcel being served. Parking is not permitted within the road right-of-way unless permitted by MOTI and a development variance permit has been issued by the RDEK permitting the parking stalls to not be on the property.

The RDEK Zoning Bylaw requires parking stalls to be no less than 2.7m wide by 6.0m deep. A loading bay is required to be no less than 3.5m in width and 9.0m in length.

Community Gathering Space

A community gathering space is proposed to provide a place for informal community interaction, structured outdoor space for smaller community events, and as structured space for larger events in combination with Edgewater Community Park which abuts the Post Office property to the west.

The community gathering space is seen as an informal outdoor space where community members can meet or where more formal events can occur. Seating and weather protection are provided to make the space suitable for year-round use.

The community gathering space does not require specific zoning and is permitted in all zones. There are no parking requirements associated with this use.

Commercial Retail Units

Opportunities for commercial retail units are limited due to the population of Edgewater and the community's desire not to encourage tourist activity at this site. The viability of the commercial retail units in the ground floor of mixed-use projects depends on several design factors and success in the initial leasing as well as the continuing operations by the retail tenants will be directly related to the degree to which these requirements are met. The success of retail space is dependant on:

- Overall building configuration
- Exposure to pedestrian and vehicular traffic
- Opportunities for signage
- Ease of fixturing and merchandising
- Availability of parking
- Appropriate mechanical, electrical and communications services to support their functions •
- Structural capacity and serviceability of unit such as:
 - Loading
 - Garbage, Recycling & Compost
 - Access to Storage
- Ability to adapt easily to change in tenant and use.

The commercial retail units shown on the development plan are to be designed in a manner that allows for their ultimate development as either residential units or commercial retail units. The actual built form will be determined if a commercial retail tenant can be confirmed for the site and their space requirements.

For the purposes of this exercise, a commercial retail unit of approximately 100m² (1076 ft²) is proposed. This space could be broken up into two smaller commercial retail units if demand requires or converted to residential use. The space could be utilized for retail uses, personal and household services (*such as beauty and barber shop*) or as a food service use.

The commercial retail unit is designed to front onto Selkirk Avenue to provide the best visibility for drive-by traffic.

The RDEK Zoning Bylaw establishes requirements for commercial retail uses. Retail uses, personal and household services and food service uses are permitted in the following zones:

- Resort Core Zone (RES-4)
- Community Commercial Zone (C-1)
- Service Commercial Zone (C-2)
- Regional Commercial Zone (C-3)

The RDEK Zoning Bylaw also establishes parking requirements for all uses. The following are required for retail uses, personal and household services and food service uses:

Parking

General Retail uses	1 per 15m ² (161.5 ft ²) of gross floor area
Personal and Household uses	
Barber and beauty shops	1 per 15m ² (161.5 ft ²) of gross floor area
Other personal and household services	1 per 10 m ² (107.6 ft ²) gross floor area
Food Service uses	
Food and beverage services	1 per 3 seat capacity

For planning purposes, the commercial retail space is assumed to be 100m² and to be used for general retail. Therefore, a total of three (3) parking spaces are required (1 space per 35m² of gross floor area)

All required parking and loading spaces must be provided on the parcel being served. Parking is not permitted within the road right-of-way unless permitted by MOTI and a development variance permit has been issued by the RDEK permitting the parking stalls to not be on the property.

The RDEK Zoning Bylaw requires parking stalls to be no less than 2.7m wide by 6.0m deep. A loading bay is required to be no less than 3.5m in width and 9.0m in length.

Attainable Non-Market Rental Units

The Edgewater community has identified a need for attainable non-market rental units.

Based upon input from the Edgewater Redevelopment Planning Committee a mix of two-bedroom and three-bedroom units are proposed. However, actual unit make-up can be based on demand at the time of construction.

The proposed attainable non-market rental units would be developed in accordance with BC Housing requirements. BC Housing has published a guide to developing housing units titled "*BC Housing, Design Guidelines and Construction Standards, 2019*"

The BC Housing Design and Construction Standards provide standards and technical guidelines for the design and construction of new buildings, conversions and renovation projects funded and financed by BC Housing. This document is intended to be a reference and baseline from which full project specifications are to be developed by the Design Team.

The goals of the BC Housing Design and Construction Standards are:

1. provide safe and secure housing that responds to needs of the residents and fosters a sense of community.

- 2. design projects that are cost effective, spatially efficient, easy to maintain.
- 3. pursue sustainable design and construction practices that balance environmental responsibility, the well-being of the users and efficient use of resources while considering economics of building construction and life cycle costs.
- 4. construct buildings which are durable and meet BC Housing’s life expectancy for the building structure and considers the service life of all building components from the perspective of life cycle costs and long-term operational efficiency.
- 5. optimize project outcomes relating to user satisfaction, timelines, and cost through a design approach which considers the needs of all stakeholders in an integrated manner throughout the project development cycle.

Dwelling units shall be designed within the following Net Unit Areas. Net Unit Area is the dwelling area calculated from the centre line of party walls, corridor walls and the outside face of the sheathing on exterior walls and includes in-suite storage. Confirm difference in definition of net area with municipality.

Unit Type	Bedrooms	NET UNIT AREA	
		Square Metres	Square Feet
Townhouse	1	56 m2	600 ft2
	2	90 m2	969 ft2
	3	111 m2	1195 ft2
	4	125 m2	1345 ft2
Apartment / Single Storey Apartment (Motel Type)	Studio	33 m2	350 ft2
	1	49 m2	525 ft2
	2	67 m2	725 ft2
	3	86 m2	925 ft2

Net Unit Areas may be increased by up to 12% to achieve wheelchair accessibility and by up to 5% for adaptable units.

Attainable non-market rental units would be developed as multi-family residential development. The RDEK Zoning Bylaw establishes requirements for development of multi-family residential units. Zoning Bylaw 3255 defines a Multiple Family Dwellings as a dwelling containing three (3) or more dwelling units. Multiple Family Dwellings uses are permitted in the following zones:

- Multiple Family Residential - Medium Density Zone (R-3)
- Multiple Family Residential - High Density Zone (R-4)
- Multiple Family Residential (Cluster) – Medium Density Zone (R-4(A))

- Multiple Family Residential – Community (Cluster) Zone (R-5)
- Golf Course / Ski Resort Development Zone (RES-2(G))
- Ski Resort/Residential Development Zone RES-2(S)
- Resort Lodge Zone (RES-3)
- Resort Core Zone (RES-4)

The RDEK Zoning Bylaw establishes minimum parcel area requirements for multiple family dwellings as follows (all multiple family dwellings must be served by a community water and community sewer system):

Minimum Parcel Area

Three (3) dwelling units	1000m ² (10,764.3 ft ²)
Four (4) dwelling units	1300m ² (13,993.5 ft ²)
Five (5) or more dwelling units	1500m ² (16,146.4 ft ²)

The RDEK Zoning Bylaw also establishes parking requirements for all uses. The following are required for multiple family dwellings:

Parking

Multiple Family Dwelling Unit	2 stalls per dwelling unit
-------------------------------	----------------------------

All required parking spaces must be provided on the parcel being served. Parking is not permitted within the road right-of-way unless permitted by MOTI and a development variance permit has been issued by the RDEK permitting the parking stalls to not be on the property. The RDEK Zoning Bylaw requires parking stalls to be no less than 2.7m wide by 6.0m deep.

Development Program Summary

Based on the preceding outline a program for development of the Post Office parcel has been developed to include a post office, commercial retail unit, community gathering space and attainable non-market rental units (ie. residential apartments).

There are only a few zones in the RDEK that permit the mix of development proposed, none of them suited to the development style envisioned. Due to the nature of the proposed development, a custom zone is proposed known as a Comprehensive Development Zone or “CD” zone. A CD zone is normally created for a specific parcel of land to allow for customized zoning that addresses the unique aspects of the proposed development and local government considerations.

The proposed CD zone is outlined in full in the Land Use Approvals section of this report. However, the following are assumed for planning purposes:

Permitted Uses

- (a) Multiple Family Dwelling
- (b) Government Services
- (c) General Retail
- (d) Food Service
- (e) Personal and Household Uses
- (f) Uses permitted under Section 4.03 of this Bylaw.

Siting

- (a) No person shall site a principal building in the CD-1 zone which has:
 - (i) a front yard less than 4.5 m (14.8 ft)
 - (ii) an internal side yard less than 1.5m (4.9 ft)
 - (iii) an exterior side yard less than 4.5 m (14.8 ft)
 - (iv) a rear yard less than 1.5m (4.9 ft)

Size and Dimensions of Buildings and Structures

- (b) No person shall site a principal building or structure in the CD-1 zone which exceeds a height of 12.0 m (39.4 ft).
- (c) No person shall site an accessory building or structure in the CD-1 zone which exceeds a height of 5.0 m (16.4 ft).

Parking

Off-street parking spaces shall be provided and maintained in accordance with the following table, where applicable. For uses not listed below, the provisions of Part 6 shall apply:

- (a) Multiple Family Dwelling Unit (Studio and One Bedroom) 1.0 stalls per dwelling unit
- (b) Multiple Family Dwelling Unit (Two Bedroom and Larger) 1.5 stalls per dwelling unit

Based on the CD zone proposed above, the following program has been developed for the Post Office property:

- The post office is proposed to be approximately 110m² (1200 ft²) and will be located on the ground floor of a building with access from Selkirk Avenue. A minimum of four (4) parking stalls and one loading stall are required for the post office.
- The commercial retail unit proposed is to be approximately 100m² (1076ft²) and will be located on the ground floor of a building with access from Selkirk Avenue. Three (3) parking stalls are required.
- A total of 534m² (5,748 ft²) of attainable non-market rental units which represent 3 two-bedroom apartment style units and 3 three-bedroom townhouse style units. Nine (9) parking stalls are required for this use.
- Public outdoor space for community gathering and events with visual and physical connection to existing park to west of property.

4.2 Considerations for BC Housing

Commercial and retail development is not normally within the purview of BC Housing. However, if the residential units on the property are developed by BC Housing (or in partnership with BC Housing) then BC Housing require certain standards to be met regarding the commercial retail units on the property.

4.3 Building Form and Architectural Concepts

Building forms for both the Post Office Property and the Vermillion Property should recognize site patterns and help define entries to interior courtyards, building entrances, public spaces and enhance the pedestrian scale. Buildings can utilize elements such as massing, materials, windows, canopies or simply different colour schemes to ensure commercial spaces are identifiable and visually distinct from residential spaces of a mixed-use.

The building form utilized for the Edgewater Community Hub has been chosen to build upon Edgewater's agricultural heritage while meeting modern building code and design requirements. Generally referred to as "Modern Farmhouse" the proposed architectural style utilizes elements of rural agrarian building forms combined with modern building materials to ensure buildings that fit within the fabric of the community. Low maintenance building materials – such as cementitious siding (Hardiplank) and metal roofs reduce operating costs for the development.

The photos shown below are intended to capture the scale of development and simple detailing proposed while utilizing building form to create a pedestrian friendly environment to encourage community gathering.



EDGEWATER

Community Hub



Photo previous page and top of this page – Retail complex in Robert's Creek, BC which includes café, post office and retail units. The configuration and scale of development is welcoming to gathering within the greenspace surrounding and the buildings.

Photo bottom this page – Market building with elements of rural commercial buildings in the East Kootenays.

Photos next page – Demonstrating elements of Modern Farmhouse which could be incorporated into design to reduce capital and ongoing maintenance costs – simplified forms and details, low-maintenance cladding, metal roofing, etc.

EDGEWATER

Community Hub



4.3.1 Vermillion Property

The development program for the Vermillion property is implemented in a single-storey building of approximately 222m² (2,390 ft²). This building is supported by an outdoor space of not less than 180m² (1,938 ft²) plus allocation for parking, sidewalks, non-accessible space (ie. mechanical area), and other considerations.

Simplified building section-elevations have been developed to illustrate building massing and layout for the child care facility (see Figure 9).




Figure 9 – Conceptual Elevations – Vermillion Property

4.3.2 Post Office Property

The development program for the Post Office property outlined previously has been implemented as shown below (see Figure 10).

The main floor of the north building includes the post office (110 m²) and the commercial retail unit (100 m²). The second floor of the north building includes three (3) – 2 bedroom rental residential units. Each unit is 67 m² in accordance with BC Housing requirements. The units are accessed from an exterior stair (which could also be enclosed).

The south building comprises three (3) – 3 bedroom rental residential units. Each unit is 111 m² (55.5 m² per floor) in accordance with BC Housing requirements.





Figure 10 – Conceptual Floorplans – Main Floor Plan (above left) and Upper Floor Plan (above, right)

EDGEWATER

Community Hub


Simplified building section-elevations have been developed to illustrate building massing and layout for the Post Office Property (see Figure 11 and Figure 12).




Conceptual East Section / Elevation



Conceptual East Section / Elevation



Conceptual East Section / Elevation




Conceptual East Section / Elevation

Figure 11 – Conceptual Elevations



*Conceptual North Elevation
Post Office and Commercial Retail Unit Frontage*



*Conceptual East Elevation
Commercial Retail Unit and
Attainable Non-Market Rental Units
with Public Interior Courtyard*

Figure 12 – Conceptual Elevations

4.4 Site Planning

4.4.1 Vermillion Property

The site plan for the Vermillion property considers the proposed building program, including requirement for outdoor space, required setbacks from property lines, parking and drop-off requirements, among other considerations.

The site plans developed for this property are constrained by required parking and property setbacks. The property setbacks within the P-1 (Public Institutional) zone require a front yard setback of 7.5m (24.6ft) along Selkirk Avenue and rear and side yard setbacks of 4.5m (14.8ft).

When the required building footprint is placed on the property, along with the requirement for outdoor space, it allows for two site plan options:

Option 1 pushes the building to the front setback and situates the required outdoor space north of the building. Parking is provided fronting the building from Selkirk Avenue. (see Figure 11, Vermillion Property - Site Plan, Option 1)

Option 2 locates the outdoor space to the south with the building to the north. Parking is provided from the lane north of the site. (see Figure 12, Vermillion Property - Site Plan, Option 2)

Other potential layouts of the property would result in an awkwardly narrow building or an overly complex (and expensive) building form.

In both options, fenced outdoor space of not less than 180m² (1,938 ft²) is required for the facility. The site plans developed include 227m² (2,443 ft²) of outdoor space.

Parking for three (3) vehicles is required in accordance with RDEK Zoning Bylaw 3255. However, parking for seven (7) vehicles is provided based on actual demand for the proposed facility. A vehicle lay-by is also proposed within the road right-of-way of Vermillion Street for drop-off and pick-up of children.

Sidewalks are proposed along Vermillion Street and fronting the child care building for access to the building, parking and the vehicle lay-by as well as for pedestrian access to the facility from the community.

Relocation of the required parking partially or wholly within the Selkirk Avenue road right-of-way would permit alternate layout options for the property but would require approval from the BC Ministry of Transportation and Infrastructure.




Figure 11 – Vermillion Property – Site Plan, Option 1

EDGEWATER
Community Hub




Figure 12 – Vermillion Property – Site Plan, Option 2

4.4.2 Post Office Property

The site plan for the Post Office property considers the proposed building program, required setbacks from property lines, and parking requirements, among other considerations.

The site plans developed for this property are constrained primarily by parking requirements. The uses proposed for the site require a total of 17 parking stalls for the proposed uses (*see Figure 13*).

The site plan developed for the property places the post office and commercial retail unit facing Selkirk Avenue to maximize exposure to the street. Eight (8) parking stalls are provided from Selkirk Avenue for these uses. A loading stall is provided from Sinclair Street for the post office and commercial retail units.

Three 2-bedroom units are provided above the post office and commercial retail unit. The units are accessed from the courtyard. The south building is configured to wrap around the corner of the site and create a partially enclosed courtyard. Three 3-bedroom townhouse units (2 storey) are provided in the south building. These units are accessed from Sinclair Street and from the lane. Nine (9) parking stalls are provided along Sinclair Street for the residential units.

A courtyard area is created by the building forms which creates opportunities for public gathering. The courtyard is designed to be open to the park to the west and could become part of the functional space of this park if the existing chainlink fence were removed. The courtyard is envisioned to provide casual space for local residents to meet and interact while also functioning as an extension of the park for organized events. Site furniture and structures such as benches, picnic tables / café tables, and overhead sun / weather protection will serve to ensure that the space is welcoming year-round.

The commercial retail units should be designed to flow through to the courtyard so that they are accessible from Selkirk Street frontage or from the courtyard. This will be particularly valuable if a food service use is viable in all, or part, of the commercial retail unit as outdoor seating could be provided in the courtyard.



EDGEWATER

Community Hub




Figure13 – Post Office Property – Site Plan


4.5 Development Phasing

Phasing development of the Post Office property may be considered based on funding availability.

Development of either building on the property will require demolition of at least part of the existing post office building. Optimally, the new post office / commercial retail building would proceed as phase one of development thereby replacing the existing post office building and maintaining this service in the community.

The attainable non-market rental units on the south portion of the property could then proceed after the north building is constructed with minimal impact on operation of the post office / commercial retail building or the second floor residential units.

Another option would be to simply proceed with the post office building (see *Figure 14 – Conceptual Elevations and Figure 15 – Post Office Property, Site Plan, Phase 1*). If this option is proposed, it is recommended that the building be situated as envisioned in the site plan to ensure suitable area is preserved for future development of the commercial / retail space and non-market rental accommodation.



*Conceptual North Elevation
Post Office Frontage*



*Conceptual East Elevation
Post Office – View from Park*

Figure 14 – Conceptual Elevations

EDGEWATER
Community Hub




Figure 15 – Post Office Property, Site Plan, Phase 1

4.6 Universal Design and Accessibility

All development should be planned, designed and built to be accessible for all people regardless of their age, size, ability or disability. If a stair and/or ramp are provided, it must be easily usable by people with reduced mobility and impaired vision. Accessibility shall be accommodated in accordance with all applicable Building Codes and BC Housing Design Guidelines and Construction Standards.

4.7 Energy Performance and Sustainability Considerations

All buildings should meet the minimum Energy Step Code Targets for new BC Housing projects. The building form and thermal performance of building elements (including architectural, structural, envelope and mechanical elements) should be carefully considered, optimizing the passive strategies in design.

4.8 Safety and Security

Safety is important for all building users. The space should be designed with safety as the primary goal. Site planning and building design should consider Crime Prevention Through Environmental Design (CPTED) strategies, including territoriality, natural surveillance activity support, and access control, as well as other recognized CPTED principles. Exterior lighting and landscape design are an integral part thereby encouraging safe access to these areas. Pedestrian areas need to be well-marked and well-lit with the source light being shielded to reduce glare, or light spillage off site or beyond parking lots and street.

5.0 Preliminary Budget

5.1 Preliminary Project Budget

A preliminary budget for development of the Vermillion property and the Post Office property has been prepared to provide order-of-magnitude costing for planning purposes. The budgets provided are intended only as a guide to gauge project feasibility. Assumptions have been made for budgeting purposes that may not represent the final vision for the sites and which may result in increased or decreased costs.

The construction industry has seen considerable inflationary pressures in the past three years. Statistics Canada has found that non-residential building construction costs rose 1.5% in the second quarter of 2023, following a 1.7% increase in the previous quarter. Year over year, construction costs for non-residential buildings in the 11-census metropolitan area (CMA) composite rose 7.0%. Skilled labour shortages, cost of materials and labour rate changes were reported by contractors as key factors impacting the construction sector. (*Statistics Canada, Building construction price indexes, second quarter 2023*). Many contractors in the Upper Columbia Valley area of the RDEK have indicated that they are feeling the impacts of these factors on project budgets and timelines.

5.1.1 Vermillion Property

Development of the Vermillion property as a child care facility will involve site servicing, construction of the child care building, building FFE (fixtures, furniture and equipment), and construction of outdoor spaces including parking and outdoor child care facilities as summarized below and as shown in *Table 5.1 – Vermillion Property – Preliminary Construction Budget*:

- Land Use Approvals are required to change the Zoning and OCP designations for the property to permit the development proposed. The allowance provided includes application fees payable to the RDEK.
- Consolidation of the property will be required prior to development. The allowance provided assumes the services of a lawyer and surveyor for the consolidation.
- A Phase 1 Environmental Assessment will be required for the property. The allowance provided assumes that no areas of potential environmental concern are identified.
- Site works / site preparation for this project would be limited to removal of existing vegetation.
- The site will require servicing with water and sewer from the community system. It is assumed that the existing services are readily accessible in the frontage roads.
- Development charges include building permit fees and fees for connection to water and sewer. Although the RDEK is the current owner of the property, budgeting for this facility assumes that the project pays all required RDEK fees and charges.
- Building construction costs include all costs for construction of the vertical building, from foundation to roof and include all interior finishes. It is assumed that the RDEK will require the building to meet Energy Step Code 4. A per square meter cost of \$4,000 (\$370/ft²) has been assumed for this facility.

- Furniture, Fixtures & Equipment will include furniture, fixtures and equipment required for operation as a child care facility – such as outfitting the kitchen, laundry, and other standard furniture. It does not include specialty equipment.
- Landscaping and Other Works includes all sidewalks, parking (gravel), fencing and landscaping but does not include any specialty equipment (such as playground equipment).
- A child care facility as proposed herein is considered a Part 3 building under the BC Building Code and the services of a registered professional architect are required. We have assumed professional fees for an architect and other required professionals (ie. structural engineer, electrical engineer, mechanical engineer, etc) at 15% of total construction costs.
- A contingency of 20% has been assumed on all construction costs.

Based on the above assumptions, and costing as shown in Table 5.1 (below) a preliminary construction budget of \$1,442,475 has been established for this facility. This valuation has been confirmed against similar building types in the Columbia Valley to ensure that the budget provided is realistic.

Table 5.1 – Vermillion Property – Preliminary Construction Budget

Description	Area	Unit Cost	Units	Cost
Land Use Approvals (Zoning)		\$10,000	allowance	\$ 10,000
Legal and Subdivision		\$10,000	allowance	\$ 10,000
Geotechnical Review		\$15,000	allowance	\$ 15,000
Environmental Assessment		\$10,000	allowance	\$ 10,000
Site Works	836 m ²	\$10,000	allowance	\$ 10,000
Site Servicing (Water / Sewer)		\$20,000	allowance	\$ 20,000
Development Charges 		\$15,000	allowance	\$ 15,000
Building Construction	222 m ²	\$4,000	per square meter	\$ 888,000
Furniture, Fixtures & Equipment	222 m ²	\$250	per square meter	\$ 55,500
Landscaping and Other Works		\$75,000	allowance	\$ 75,000
SUB-TOTAL				\$ 1,108,500
Professional Fees (15%)		15%	percentage	\$ 166,275
Contingency (20%)		20%	percentage	\$ 221,700
TOTAL				\$ 1,496,475

5.1.2 Post Office Property

Development of the Post Office property as envisioned will involve site servicing, construction of the commercial and residential buildings, building FFE (fixtures, furniture and equipment), and construction of outdoor spaces including parking and community gathering area as summarized below and as shown in *Table 5.2 – Post Office Property –Preliminary Construction Budget*:

- Land Use Approvals are required to change the Zoning and OCP designations for the property to permit the development proposed. The allowance provided includes application fees payable to the RDEK.
- Consolidation of the property will be required prior to development. The allowance provided assumes the services of a lawyer and surveyor for the consolidation.
- A Phase 1 Environmental Assessment will be required for the property. The allowance provided assumes that no areas of potential environmental concern are identified.
- Geotechnical assessment of the property is proposed to address the ground settling behind the post office. An allowance for preliminary geotechnical assessment has been provided.
- Demolition and Remediation includes an allowance for demolition and disposal of the post office building and credit union building. This allowance also includes assessment of the building for potential asbestos containing materials or other hazardous materials. Demolition costs will increase depending on the type and quantity of hazardous materials discovered.
- Site works / site preparation for this project would be limited to clearing and grubbing of the property.
- The site will require servicing with water and sewer from the community system. It is assumed that the existing services are readily accessible in the frontage roads.
- Development charges include building permit fees and fees for connection to water and sewer. Although the RDEK is the current owner of the property, budgeting for this facility assumes that the project pays all required RDEK fees and charges.
- Building construction costs include all costs for construction of the vertical building, from foundation to roof and include all interior finishes. It is assumed that the RDEK will require the building to meet Energy Step Code 4. Statistica.com found that current costs for townhouse construction in British Columbia in 2022 range from \$2,580 - \$4,440/m². Construction costs for these buildings have been assumed as:
 - \$3,500 per square meter for the commercial / retail component.
 - \$3,250 per square meter for the attainable non-market rental units located above commercial.
 - \$3,500 per square meter for the self-contained (stand-alone) attainable non-market rental units
- Furniture, Fixtures & Equipment will include furniture, fixtures and equipment required for the attainable non-market rental units – such as outfitting the kitchen, laundry, and any built-in furniture.
- Landscaping and Other Works includes all sidewalks, parking (gravel), fencing and landscaping but does not include any specialty equipment (such as playground equipment).

- The commercial retail building with housing above is a Part 3 building under the BC Building Code and the services of a registered professional architect are required. We have assumed professional fees for an architect and other required professionals (ie. structural engineer, electrical engineer, mechanical engineer, etc) at 10% of total construction costs.
- A contingency of 20% has been assumed on all costs.

Based on the above assumptions, and costing as shown in Table 5.2 (below) a preliminary construction budget of \$3,977,025 has been established for Post Office property.

Table 5.2 – Post Office Property – Preliminary Construction Budget

Description	Area	Unit Cost	Units	Cost
Land Use Approvals (Zoning)		\$10,000	allowance	\$ 10,000
Legal and Subdivision		\$10,000	allowance	\$ 10,000
Environmental Assessment		\$10,000	allowance	\$ 10,000
Geotechnical Assessment		\$15,000	allowance	\$ 15,000
Demolition and Remediation		\$60,000	allowance	\$ 60,000
Site Works		\$10,000	allowance	\$ 10,000
Site Servicing (Water / Sewer)		\$30,000	allowance	\$ 30,000
Development Charges		\$15,000	allowance	\$ 15,000
Building Construction (Commercial)	210 m ²	\$ 3,500	per square meter	\$ 735,000
Building Construction (Residential)	201 m ²	\$ 3,250	per square meter	\$ 653,250
Building Construction (Residential)	336 m ²	\$ 3,500	per square meter	\$ 1,176,000
Furniture, Fixtures & Equipment		\$ 100,000	allowance	\$ 100,000
Parking Lot and Driveways		#35,000	allowance	\$ 35,000
Landscaping and Other Works		\$200,000	allowance	\$ 200,000
SUB-TOTAL				\$ 3,059,250
Professional Fees (10%)		10%	percentage	\$ 305,925
Contingency (20%)		20%	percentage	\$ 611,850
TOTAL				\$ 3,977,025



The community may also consider development of a stand-alone post office on the Post Office property as the first phase of a multi-year redevelopment of the property. Development of a stand-alone post office would require site servicing, construction of the post office building, building FFE (fixtures, furniture and equipment), and parking as summarized below and as shown in *Table 5.3 – Post Office Property –Preliminary Construction Budget, Phase 1:*

- Land Use Approvals are required to change the Zoning and OCP designations for the property to permit the development proposed. The allowance provided includes application fees payable to the RDEK.
- Consolidation of the property will be required prior to development. The allowance provided assumes the services of a lawyer and surveyor for the consolidation.
- A Phase 1 Environmental Assessment will be required for the property. The allowance provided assumes that no areas of potential environmental concern are identified.
- Geotechnical assessment of the property is proposed to address the ground settling behind the post office. An allowance for preliminary geotechnical assessment has been provided.
- Demolition and Remediation includes an allowance for demolition and disposal of the post office building and credit union building. This allowance also includes assessment of the building for potential asbestos containing materials or other hazardous materials. Demolition costs will increase depending on the type and quantity of hazardous materials discovered.
- Site works / site preparation for this project would be limited to clearing and grubbing of the property.
- The site will require servicing with water and sewer from the community system. It is assumed that the existing services are readily accessible in the frontage roads.
- Development charges include building permit fees and fees for connection to water and sewer. Although the RDEK is the current owner of the property, budgeting for this facility assumes that the project pays all required RDEK fees and charges.
- Building construction costs include all costs for construction of the vertical building, from foundation to roof and include all interior finishes. It is assumed that the RDEK will require the building to meet Energy Step Code 4. Construction costs for the post office have been assumed at \$3,500 per square meter. 
- Landscaping and Other Works includes all sidewalks, parking (gravel) and landscaping. 
- The post office building is a Part 3 building under the BC Building Code and the services of a registered professional architect are required. We have assumed professional fees for an architect and other required professionals (ie. structural engineer, electrical engineer, mechanical engineer, etc) at 15% of total construction costs.
- A contingency of 20% has been assumed on all costs.

Based on the above assumptions and costing as shown in Table 5.3 (below) a preliminary construction budget of \$803,500 has been established for Phase 1 (Post Office) only.

Table 5.3 – Post Office Property – Preliminary Construction Budget, Phase 1

Description	Area	Unit Cost	Units	Cost
<i>Land Use Approvals (Zoning)</i>		<i>\$10,000</i>	<i>allowance</i>	<i>\$ 10,000</i>
<i>Legal and Subdivision</i>		<i>\$10,000</i>	<i>allowance</i>	<i>\$ 10,000</i>
<i>Environmental Assessment</i>		<i>\$10,000</i>	<i>allowance</i>	<i>\$ 10,000</i>
<i>Geotechnical Assessment</i>		<i>\$15,000</i>	<i>allowance</i>	<i>\$ 15,000</i>
<i>Demolition and Remediation</i>		<i>\$60,000</i>	<i>allowance</i>	<i>\$ 60,000</i>
<i>Site Works</i>		<i>\$10,000</i>	<i>allowance</i>	<i>\$ 10,000</i>
<i>Site Servicing (Water / Sewer)</i>		<i>\$15,000</i>	<i>allowance</i>	<i>\$ 15,000</i>
<i>Development Charges</i>		<i>\$5,000</i>	<i>allowance</i>	<i>\$ 5,000</i>
<i>Building Construction (Commercial)</i>	<i>110</i>	<i>\$3,500</i>	<i>per square meter</i>	<i>\$ 385,000</i>
<i>Furniture, Fixtures & Equipment</i>		<i>\$25,000</i>	<i>allowance</i>	<i>\$ 25,000</i>
<i>Parking Lot and Driveways</i>		<i>\$25,000</i>	<i>allowance</i>	<i>\$ 25,000</i>
<i>Landscaping and Other Works</i>		<i>\$25,000</i>	<i>allowance</i>	<i>\$ 25,000</i>
SUB-TOTAL				\$ 595,000
<i>Professional Fees (15%)</i>		<i>15%</i>	<i>percentage</i>	<i>\$ 89,250</i>
<i>Contingency (20%)</i>		<i>20%</i>	<i>percentage</i>	<i>\$ 119,000</i>
TOTAL				\$ 803,500

6.0 Regulatory Approvals

6.1 Land Use Approvals

6.1.1 Vermillion Property

Zoning Bylaw 3255 defines Group Day Care as a facility for the temporary care of children licensed as Group Child Care (various ages) or Multi-age Child Care under the Community Care and Assisted Living Act and the Child Care Licensing Regulation. Group Day Care uses are only permitted in the Public Institutional (P-1) Zone.

A copy of the RDEK's P1 Zone is included in Appendix E of this report.

6.1.2 Post Office Property

As noted previously, there are only a few zones in the RDEK that permit the mix of development proposed, but none of them are well suited to the development style envisioned. Due to the nature of the proposed development, a custom zone is proposed known as a Comprehensive Development Zone or "CD" zone. A CD zone is normally created for a specific parcel of land to allow for customized zoning that addresses the unique aspects of the proposed development and local government considerations.

The proposed CD zone is outlined below:

COMPREHENSIVE DEVELOPMENT ZONE 1: CD-1

Purpose

The purpose of this Comprehensive Development Zone is to facilitate development of a comprehensively planned mixed-use commercial residential development, providing government services in the form of a post office and limited retail opportunities with apartment and townhouse housing forms, and public recreation and gathering space.

(1) Area of Application

Those lands shown as CD-1 on the CD-1 Zoning Map, Schedule A.

(2) Permitted Uses

Within the CD-1 zone, the following uses only are permitted:

- (a) Multiple Family Dwelling*
- (b) Government Services*
- (c) The following Retail Trade industries:*
 - (i) food, beverage, and drug store;*
 - (ii) shoe, apparel, fabric, and yarn store;*
 - (iii) household furniture, appliance, and furnishing store;*
 - (iv) antique shop*
 - (v) bicycle shop - retail and repair*
 - (vi) gift, novelty and souvenir store*
 - (vii) art gallery and artists' supply store*
 - (viii) camera and photography shop*
 - (ix) travel service*
 - (x) general retail store*
 - (xi) other retail stores*

- (d) *Beauty and barber shop*
- (e) *Food Service*
- (f) *Local and Regional Park and Open Space*
- (g) *Uses permitted under Section 4.03 of this Bylaw.*

(3) **Accessory Uses**

- (a) Other uses, buildings and structures accessory to a permitted use.

(4) Density

No person shall site buildings and structures on a parcel in the CD-1 zone which exceed a floor area ratio of 3.5.

(5) **Siting**

No person shall site a building or structure in the RES-4 which has:

- (a) a front yard less than 4.5 m (14.8 ft)
- (b) an internal side yard less than 1.5m (4.9 ft)
- (c) an exterior side yard less than 4.5 m (14.8 ft)
- (d) a rear yard less than 1.5m (4.9 ft)

(6) *Size and Dimensions of Buildings and Structures*

- (a) No person shall site a principal building or structure in the CD-1 zone which exceeds a height of 12.0 m (39.4 ft).
- (b) No person shall site an accessory building or structure in the CD-1 zone which exceeds a height of 5.0 m (16.4 ft).

(7) Off-Street Parking

Off-street parking spaces shall be provided and maintained in accordance with the following table, where applicable. For uses not listed below, the provisions of Part 6 shall apply:

- (a) Multiple Family Dwelling Unit 1.5 stalls per dwelling unit

(8) Other Regulations

- (a) *All persons carrying out a use permitted in the CD-1 zone shall comply with the relevant provisions of Parts 4, 5, and 6 of this Bylaw.*
- (b) *All persons carrying out a use permitted in the CD-1 zone shall comply with the relevant provisions of Section 4.12 of this Bylaw with respect to screening of outdoor storage.*
- (c) *No person shall use or permit the use of any portion of a parcel in the CD-1 zone for the wrecking and repair of vehicles or for the storage of derelict vehicles.*

6.2 Subdivision

Consolidation of the three parcels that make up the Vermillion property and the seven parcels that make up the Post Office property (or legal binding of titles) is required to obtain a building permit as the RDEK will not issue a building permit for a building or structure that straddles property lines.

6.2.1 Vermillion Property

The Vermillion property should be consolidated into one parcel prior to development. The consolidation of this parcel can be completed under section 100(1)(b) of the Land Title Act and does not require submission of an application for subdivision or approval from the RDEK (except as owner of the property) or MOTI.

6.2.2 Post Office Property

The final legal form of development for this parcel will be based on the ownership model and the involvement of BC Housing or other potential partners.

Regardless of the final ownership model, the property should be consolidated into one parcel prior to development. The consolidation of this parcel can be completed under 100(1)(b) of the Land Title Act and does not require submission of an application for subdivision or approval from the RDEK (except as owner of the property) or MOTI.

Consolidation should not be undertaken until environmental clearance (ie. Phase 1 Environmental Assessment) for the property has been obtained.

6.3 Environmental Clearance

A Phase 1 Environmental Assessment will be required prior to any development of either property if Provincial or Federal funds are utilized for the development of attainable non-market rental units or a child care facility.

6.4 Geotechnical Assessment

As noted by Columbia Valley Engineering, a geotechnical assessment of the Post Office property should be undertaken to confirm the cause of any ground settlement and to ensure that this issue does not impact any future development of the property.

7.0 Next Steps

7.1 Next Steps

Based on the level of community support apparent at the February 6, 2024 community open house, we recommend that the Edgewater Redevelopment Planning Committee continue to move this project forward with the cooperation of the RDEK.

7.1.1 Vermillion Property

Potential next steps for development of the Vermillion property include:

1. RDEK Board to prioritize this project and assign staff to assist the Edgewater Redevelopment Planning Committee with moving forward to development of property.
2. RDEK to determine potential ownership and operational models for a child care facility on RDEK property.
3. Complete subdivision (consolidation) of property to ready for future development as child care facility.
4. Complete land use amendments for property to ready for future use as child care facility.
5. RDEK and Edgewater Redevelopment Planning Committee research and develop partnerships with local non-profit groups that can assist with development or operational capacity for new child care facility.
6. RDEK and Edgewater Redevelopment Planning Committee research and develop potential funding opportunities from Provincial and local government and other sources.
7. RDEK and Edgewater Redevelopment Planning Committee to determine potential service area for funding project and creation of service area.
8. Engagement of project manager by the RDEK when project has secured suitable funding to move forward.
9. RDEK and Edgewater Redevelopment Planning Committee complete detailed design of the facilities, including engagement of architect and other professionals.

7.1.2 Post Office Property

Potential next steps for development of the Post Office property include:

1. RDEK Board to prioritize this project and assign staff to assist the Edgewater Redevelopment Planning Committee with moving forward to development of property.
2. RDEK to determine potential ownership and operational models for a post office facility, commercial retail uses and attainable housing on RDEK property.

3. Complete subdivision (consolidation) of property to ready for future development.
4. Complete land use amendments for property to ready for future use to include post office facility, commercial retail uses and attainable housing.
5. RDEK and Edgewater Redevelopment Planning Committee research and develop partnerships with local non-profit groups that can assist with development or operational capacity for new attainable housing.
6. RDEK and Edgewater Redevelopment Planning Committee to meet with Canada Post to define the roll of Canada Post, determine Canada Post building standards and obtain commitment from Canada Post for long-term lease of post office building.
7. RDEK and Edgewater Redevelopment Planning Committee research and develop potential funding opportunities from Provincial and local government and other sources.
8. RDEK and Edgewater Redevelopment Planning Committee to determine potential service area for funding project and creation of service area.
9. Engagement of project manager by the RDEK when project has secured suitable funding to move forward.
10. RDEK and Edgewater Redevelopment Planning Committee complete detailed design of post office, commercial retail uses and attainable housing, including engagement of architect and other professionals.

Appendix A

**Working Towards a Sustainable Economy in Edgewater,
Community Engagement Report,
Feasibility Study for Community Hub Report,
November 2010**



Centre for Innovative &
Entrepreneurial Leadership

Working Towards a Sustainable Economy in Edgewater

Community Engagement Report

Feasibility Study for Community Hub Report

November 2010

Funding by:



Working Towards a Sustainable Economy in Edgewater

Table of Contents

Summary	3
Objectives of Project	4
Community Engagement - Project Elements	4
Feasibility Study – Project Elements	4
Project Guided by	5
Community Engagement Session Public Meeting I - June 22, 2010	5
Agenda	5
Objectives of the First Session	6
Other Economic Development Information	6
Summary of Notes from Group Activities	8
Q1 Untapped opportunities	8
Q2 Distinct from other communities in the area	12
Q3 What ideas would the community support.....	14
Edgewater Community Vision & Economic Revitalization Survey.....	16
Marketing	22
Entertainment/ Culture	22
Other	22
Social/ Cultural.....	23
Nature/ Environment.....	23
Community Session II - October 13, 2010	26
Possible Short Term Actions	28
Conclusion	30
Feasibility Study	31
Community Hub - Determining Community Uses	31
Space Requirements and Probable Rent Generation	33
Notes & Assumptions	33
Feasibility Considerations	35
Construction Costs	35
Estimated operating costs.....	35
Estimated down Payment	36
Mortgage.....	36
Total Costs vs Possible Rents Generated	36
Conclusion	37
Options	37
Appendices	38
1. Reality Checks from 3 Community Initiatives from Oct. 13/10 Session	38
2. PowerPoint – June 22/10 Community Meeting.....	38
3. PowerPoint – Oct. 13/10 Community Meeting	38

Summary

RDEK Director Gerry Wilkie and several citizens of Edgewater initiated a project in the spring of 2010 to determine the feasibility of replacing the community's deteriorating post office building with a vital community "hub", housing the post office and several other needed community services and/or businesses. It was believed that the building of a hub might also act as a catalyst for establishment of other businesses on available commercial land in this core area.

Edgewater had experienced the loss of Kootenay Savings Credit Union (KSCU) branch to Radium and it was believed that the loss of the post office would be detrimental to the future of the community. Use of the former KSCU building (which had been vacant since it was donated to the community in 2009 and adjacent to the post office building) was also to be factored into the community "hub" plan. Currently, the community has only one storefront business - a general store.

CIEL (Centre for Innovative & Entrepreneurial Leadership – www.theCIEL.com), mainly through Executive Director Mike Stolte, was contracted to undertake a community engagement process - public meetings, a survey, and key stakeholder interviews - to determine community needs in the broader context of creating a healthy economy for Edgewater.

Working with a community advisory committee (AC) composed of Gerry Wilkie, Jesse Simpkins, Graham Wake, Tammy Tutte, Jessica Breeze, and Barry Moore, CIEL was to use the findings to determine acceptable and possible hub uses and determine whether the replacement of the building was feasible given the probable rents that could be generated. Further, through the engagement process CIEL was to identify initiatives that could be used to generate a healthy and sustainable economy in Edgewater.

The process was funded by the Columbia Basin Trust and the RDEK.

The report is:

1. a summary of the community engagement process, its outcomes (which informed the feasibility study) and identification of initiatives that would contribute to a healthy vital economy and community in Edgewater
2. a feasibility study on the replacement of the post office building with a community hub

Objectives of Project

- ☐ Project will identify strategies and projects that will build a healthy economy in Edgewater using
 - community meeting,
 - survey,
 - series of interviews,
 - a review of demographics, trends, etc.
- ☐ Help to strategize on a potential community hub building in site of current post office
- ☐ Conduct feasibility of construction of community hub as replacement for post office building

Community Engagement - Project Elements

Element	Sub-Element
Research	• Research, review & synthesize (for presentation) best practices in community centres/hubs
	• Demographic review, analysis of community & other relevant studies
	• Planning, design, & meetings with Gerry Wilkie (&/or Advisory Committee)
Public Consultation I	• Survey design, survey of public opinions (on-line & hard copy) & survey analysis in summer of 2010
	• Individual interviews of key stakeholders (8-10) over course of summer 2010
	• Facilitation of public meeting with prep, write-up, etc. (June 22/10)
Report	• Writing report with consultation from Gerry Wilkie &/or Advisory Committee
Public Consultation II	• Facilitation of public meeting II (reporting back to community) by Advisory Committee – (Oct. 13/10)
Finalization of Report	• Finalization of Report

Feasibility Study – Project Elements

Element	Sub-Element
Identification of Possible tenants	• Working with Gerry Wilkie (&/or Advisory Committee) to identify (& locate) possible tenants
Analysis	• Business analysis determining what Edgewater can support
Financing	• Review of financing options
Contractor Options/Report	• Review of options and final report

Project Guided by

The project has a broad-based steering committee made up of representatives from the community. Both funders, the RDEK and CBT, served in an ex-officio capacity attending some meetings and community sessions. The project was led by RDEK Director Gerry Wilkie.

Community Engagement Session Public Meeting I - June 22, 2010

Approximately 40 people attended this public meeting at Edgewater Community Hall. It was advertised via poster, newspaper, e-mail and word of mouth. (See attached PowerPoint in Appendices for demographic and other information)

Agenda

Time	Agenda Item	Lead
7:00-7:20	Introductions, Thank the sponsors, Overview & Objectives of Session	Gerry & Mike
7:20-8:00	Where we are – Demographic & Economic Context, Current Thinking on Economic Development, Other successful hub projects	Mike
8:00-9:15	Identifying: ▪ Economic Drivers, ▪ Untapped Opportunities ▪ Hub Ideas Small Group Work & Report Back to the Whole	Mike
9:15-9:30	Next steps, Check-out & Conclusion	Mike & Gerry



Objectives of the First Session

- Inform participants of the project background (Gerry Wilkie & committee, CBT), the context of the area (demographics, economics), current thinking on economic development & the process
- Instil a sense of shared responsibility for the economic future of Edgewater
- Initiate a broad conversation on generating a healthy economy in a safe forum
- Be inclusive of all segments and sectors of the community
- **Identify key future drivers of future economic activity**
- **Identify untapped community, business and economic development opportunities**
- **Generate ideas for hub (e.g. businesses)**
- Use forum as a an opportunity to identify possible new businesses, tenants for community hub building

Other Economic Development Information

Mike reviewed some best practices in economic development:

Economic Development 101

- "The best chance of survival for the human race is self-reliant local development."
John Bryden, President, International Rural Network at the 2009 OECD Rural Development Conference

- “Rural communities can only succeed if they harness their community entrepreneurs: those individuals who work to build the community's bottom line”

Mike Stolte, Canadian Rural Revitalization Foundation (CRRF)
President - address to 2006 Think tank on the Future of Rural Canada

OECD – Only 3 strategies that work for rural economic diversification

1. Innovation (sharing knowledge, linking business to info & assistance, productivity improvement, new products & services)
2. Building Human Capital (training & education)
3. Cluster Development (helping related businesses gain from collaboration)

Most effective economic development strategies in rural (Center for Rural Entrepreneurship [CRE] – based out of Nebraska)

- Business Retention & Expansion (BR + E)
- Entrepreneurship (e.g. Business Vitality Initiative – BVI)

“Entrepreneurship should be the bedrock for economic development. Creating an entrepreneur-friendly community also makes it easier to attract & retain industry and other businesses.”

Summary of Notes from Group Activities

NOTE: The summary below represents the collected answers from the community meetings. Where possible, similar ideas are grouped together. People worked in tables of 6-10 participants to identify:

1. Untapped Opportunities
2. How is Edgewater distinct from other communities in the area?
3. What ideas would the community support?



Q1 What are the untapped opportunities in Edgewater? How might these be incorporated into a central hub?

IDEAS FOR A CENTRE

Outdoor recreation centre—trails

- Interpretive adventure hikes, raft, canoe
- Tours—natural features, wetlands, flume, wildlife, x-c skiing, running, aerobics
- Educational centre—bio-research station

Historic centre—heritage events

- May day fair
- Harvest festival

Sales centre (admin.) (recreational) (entrepreneurial and artisan)

- Guiding
- Stables
- Rafting
- Canoeing
- Bird watching

Performance centre

- Music teaching/arts
- Rehearsal space
- Festivals (comedy, plays, music)
- Music (outdoor amphitheatre)
- Make better use of community hall—plays, teaching, music

Garden centre/community garden (x 2)

- School involvement (extra garden space donated)
- Food co-op
 - Root cellar storage
 - Produce
- Open market—year-round
- Agricultural projects

Central office/business centre

- Central office for home based businesses/list of above
- Accountant (office services)
- Accounting (large amt. of home based businesses)
- Fax
- Copy
- ATM (x 4)
- Who are the 87 home businesses?
- Central registry for listing skills and people who need them
- Post Office: sell Calgary Sun (income idea), Purolator
- Post office

Visitors Centre

Children & Youth (9 responses)

- Day care
- Day care—children—elder adult
- Day care—library/computer
- Daycare/preschool
- Childcare
- Kids camps—outdoor movie nights

- Opportunities for teenagers—dances, sports, hobbies, arts, “hanging out
- Youth area for 4 – 12 yr olds
- Youth activities (structured adventures)
 - Canoeing
 - Hikes
 - Local industries
 - Flume hike

Coffee shop (6 responses)

- Coffee shop/internet café/art gallery
- Lunch/coffee shop
- Coffee shop—gathering place—take out lunches etc
- Internet café—coffee shop
- Bakery (see coffee shop)
- Restaurant

Health & Wellness (6 responses)

- Pharmacy/nurse/doctor (small clinic)
- Doctor, dentist
- Physio fitness
- Pharmacy—deliver drugs
- Health clinic
- Health improvement centre
 - Physio
 - Chiro
 - Massage
 - Acupuncture
 - etc

Services (4 responses)

- Garage—change tires, gas tune-up
- Home handyman—carpenter
- Yard maintenance, snow removal
- Clean house—central registry

Recreation (4 responses)

- Swimming pool—water safety activities
- Gym/indoor rec
- Flume races—snowshoe softball
- Trails—bikes

Hair salon (3 responses)

Pub (2 responses)

- Pub/café restaurant –historic
- Pub/Lounge
 - Signage at Radium 4 corners

Education (2 responses)

- What can you teach? Child involved
- Training—trades, mining, work experience, forestry, machinery, elder care

Radio (2 responses)

- Local radio station
- Broadband

Misc.

- Community pride—beautification
- Library/study area
- Proper library/reading room
- Video store
- Recycling
- Artists loop store
- Satellite police presence (x2)
- Edgewater Days—parade etc
- Columbia Valley Orchards
- Seed potatoes
 - Olds College (research)
- Seniors Home (Home Care)
- New Round about at entrance to Edgewater (Columbia, Selkirk, Station Rd., Valley Edge, Riverview)
 - Beautified with flowers
- Cannery
 - Coffee shop
 - Bakery
 - Pizza
- Of businesses in Edgewater:
 - Community farmer's market
 - Wood tailings i.e. frames, angels, artisans, wood art

Top Picks

- Entrepreneurial & artisan centre, includes:
 - Rec sales admin (outdoor excursions)
 - Accounting (large amt. of home based businesses) (x 2)
 - Fax/copy machines (x 2)
- ATM (x 2)
- Day care/preschool (x 2)—library/computer

- Pub/café restaurant –historic (x 2)
- Sales centre
- New building with commercial tenants, post office, library, day care
- Rental units on top floor
- U-shaped building with courtyard
- Central registry for listing skills and people who need them
- Training—trades, mining, work experience, forestry, machinery, elder care
- Library/study area
- Health improvement centre
- Physio, chiro, massage etc, set day a week
- Seed potatoes
- Cannery
- Seniors Home (Home Care)
- Visitors centre
- Outdoor recreation centre
- Internet café—coffee shop
- Garden centre/community garden



Q2 How are we distinct from other communities in the area?

Quality of community (19 responses)

- Friendly, safe atmosphere
- Relaxed tolerant attitudes
- Year-round neighbours
- Community spirit

- Neighbours—1st name basis
- All homes are full (therefore it's a real community)
- Permanent residents
- Committed to the community
- Attracts youthful families
- Less congested—beautiful scenery
- Good community spirit
- It's the people! Friendly town "the friendliest town in the Kootenays"
- Lack of retail & pro services
- Peace & quiet atmosphere
- Barter—people look after each other
- Community concern—health well being, safer
- More accepting of newcomers
- Low crime rate

Location (12 responses)

- Beauty, rural life
- Quiet, content
- Slightly "off the beaten track"
- Quiet but convenient location
- Rural, quiet, country
 - Style, lifestyle, scenery
 - Most of the residences are primary residences
 - Accessible to golf, hiking, fishing, bird watching, horse riding
 - It's a small town
 - Safe
 - Amenities
 - Presently no pub
- Landmark: Indian Face Mtn
- Year round recreational opps
 - Park
 - Golf course
 - Rink
 - Field
 - Hall
- Wilderness (outfitters! Guides)
- RV park
- Flume!
- Wilderness at your doorstep (proximity)
- No major natural hazards

School (5 responses)

- School/store/post office
- Edgewater school

- Family based—good for kids
- Good school
- Elementary
 - Good town for kids to grow-up in

Misc.

- Very creative population
 - Artists
 - Writers
 - Musicians
- Spine of the valley (Edgewater supports the rest of the valley)
- Water/sewer
- Housing affordable (x 3)
- Fire protection-fire hall
- Impressive first resp. team
- Woodex mill
- Basic amenities
- Cooperative community projects
 - Open market
- Opportunity for local food sufficiency
- Locally grown food
- Linked to land base & tradition:
 - Outdoors
 - Musicians
 - Artisans
 - Trades
- 3 ½ mgd flume



Q3 What ideas would the community support?

- Daycare
- Coffee shop & bakery
- (Internet facilities)
- Business registry

- Neighbourhood pub

Business/services who might use/ rent space in hub (sign-up sheet)

Attendees listed seven existing businesses that might be considered a fit for the hub.

Edgewater Community Vision & Economic Revitalization Survey

A community survey was posted on-line & delivered to each household in Edgewater during a 3-4 week period in the summer of 2010. Approximately 30 responses were received (collected at Pips Store). The following summarizes the results (Number of responses in columns).

1. Name Three Words to Describe Edgewater

▪ Quiet, peaceful, serene	11
▪ Beautiful, picturesque	6
▪ Friendly	5
▪ Bedroom community	4
▪ Safe	2
▪ Family oriented	2
▪ Potential	2
▪ Quaint, rustic	2
▪ A few rednecks	1
▪ Affordable housing	1
▪ Agriculturally-based master plan	1
▪ Apathetic	1
▪ Away from busy centres	1
▪ Clique (SDTP)	1
▪ Community	1
▪ Community spirit	1
▪ Creative	1
▪ Diverse	1
▪ Economic	1
▪ Inviting to tourists if tourist attractions become available	1
▪ Local	1
▪ Traditional heritage values vs. apathy-disrespectful	1
▪ Natural	1
▪ Nice	1
▪ Pristine	1
▪ Private	1
▪ Removed	1
▪ Rural	1

▪ Simple	1
▪ Stable	1
▪ Static	1
▪ Under-established	1
▪ Walkable - convenient	1
▪ Small town	1
▪ Junky	1

2. What are the two greatest assets in Edgewater NOT used to potential?

▪ The river access to river- 4 canoeing- 1 bird watching-1 clean up launch area- 1 day float trips- 1	8
▪ Trails access- 2 hiking and skiing-1 biking- 1, wetlands and railroad-1	5
▪ Community hall--more diverse activities	5
▪ Ball diamond/rink	4
▪ Library	2
▪ Park	2
▪ Beautiful views of wetlands, mountains, night sky	1
▪ Tourist attractions (advertising) e.g. hiking, wetlands, river, photography	1
▪ Commercial space	1
▪ Quaint, "small town" feel	1
▪ Edgewater elementary school	1
▪ The corner lot across from Pips	1
▪ Commercial property	1
▪ Vegetation (incl. decorative) in central area	1
▪ Nature	1
▪ Nature/birdsong	1
▪ Post office building	1
▪ Agricultural capacity, viz., irrigation flume use	1
▪ Agricultural - cleared irrigated farmland, decent climate, long established Open Market	1

▪ Deep-rooted history	1
▪ Playground area (needs more attractions)	1
▪ Highway	1
▪ Quiet peaceful mountain town	1

3. List the business opportunities you feel the community could support

▪ Coffee shop, restaurant, etc. coffee shop- 6 restaurant- 6 with bakery- 5 family, no alcohol- 3 with internet- 2 with deli-1 with artisan displays-1	26
▪ Pub/bar	10
▪ Daycare	8
▪ Eco-tourism - river/wetland tours/hikes/bird-watching	2
▪ Shared health care centre- doctors, clinic, therapists, physio /chiropractor etc.	2
▪ Hotel, motel,	1
▪ Tennis/squash court	1
▪ Store that has what Pip's doesn't	1
▪ Retail co-op - one store, several tenants	1
▪ Pharmacy	1
▪ Outdoor guided excursions - by canoe, horseback, foot	1
▪ Organic gardening co-op: food supplies, flour mill, quick freezer	1
▪ More business (garage?)	1
▪ Medical clinic - maybe 2 days a week	1
▪ Larger grocery store	1
▪ Gym	1
▪ Fresh fruit stand in the summer	1
▪ Equestrian facility with a covered arena	1
▪ Driving school -- all classes	1
▪ Crafts, artisan, displays	1
▪ Artisan/farmer's market	1
▪ Car /truck wash	1

▪ Bigger corner store/gas station	1
▪ Bank/financial institution	1
▪ Bakery/ice cream or micro-brewery	1
▪ B & B	1
▪ Agriculture production - meat, vegetable, grains and hay, including the use of greenhouses	1

4. What do you believe will be the 2 most important drivers of the economy for Edgewater over the next 10 years?

▪ Tourism	13
▪ Forestry	6
▪ Construction	5
▪ Agriculture	3
▪ Younger families moving here	2
▪ Lumbering - sawmills, timber-framing, log-building	1
▪ Education/knowledge based activities/bio-eco research	1
▪ Whatever drives the rest of the valley	1
▪ Keep it affordable	1
▪ Music	1
▪ Garage	1
▪ Small businesses esp. service industries	1
▪ Employment (new businesses)	1
▪ Small businesses	1
▪ Trades	1
▪ Industry	1
▪ Recreation properties- retirement living	1
▪ Retirement/seasonal	1
▪ Open market	1
▪ Keep utilities and taxes down or people will not stay	1

5. Thinking about businesses and services being located in a central area or community hub (e.g. along a main street like Selkirk Ave. or around the Post Office area), what businesses or services would MOST benefit the community if located here?

Food service coffee shop- 8 restaurant- 3 pub- 2	21
---	----

internet café- 1 bakery- 1 various mixes of the above- 5	
Daycare	7
Post office	3
Medical clinic with pharmacy and dentist	3
Artisan workshop/retail store	2
Auto mechanic	2
Bank	2
Hotel, motel	1
Trades Association business centre - directory and accountant services	1
Outdoor adventures (not motorized) hiking, canoeing, kayaking, horseback riding, ski touring...	1
Outdoor tours co-op office	1
Gym	1
Butcher	1
Library	1
Youth centre	1
Garden Centre - natural foods supply, shared flour mill, quick freezer	1
Attractive buildings needed	1
The problem is profitability	1
Service station with car wash and convenience store w/ liquor outlet [video rentals]	1
Local produce outlet - not big chain grocery, but place to buy locally grown food	1
Recreation centre	1
Hair salon	1
Pool hall	1
Senior housing development (low income)	1
Micro-brewery/ice creamery	1
Central office registry/administration services	1
After school program	1

6. List up to 3 other ideas you believe could help Edgewater become more economically self-sufficient.

Retail, business
▪ A co-op market
▪ Agricultural co-op
▪ Cozy place to eat inside open 7 – 11

▪ More businesses
▪ Office spaces for smaller businesses
▪ Pub/restaurant - social gathering place availability of food & meals
▪ Repair and fabrication trades building (could keep farm and mill equipment in shape, produce new items)
▪ Retail co-op
▪ Local produce
▪ Small business registry
▪ Creating jobs to keep people home
▪ Expansion of Pip's
▪ Develop a trades association to share overhead and job opportunities
Infrastructure
▪ Beautify the area around the community centre with plants and trees
▪ Improve the roads (they have steadily deteriorated and look shabby)
▪ Rezone an area into LIGHT Industrial to accommodate a business offering long-term capability.
▪ Ban large trucks from parking & idling in community [no one wants to live next door to trucks idling at 3 - 4 am or shaking their homes!]
▪ Solar collectors
▪ Campground
▪ Renovate post-office/library area (haven't changed in 14 years we've lived here)
▪ Change RDEK regulations re small livestock, protect water supply for market gardens.
▪ Community gardens
▪ Community gardens. (reduces driving for groceries) supports community interaction.
▪ Community green house
▪ Building - where people could show & tell their art work, baking, veggies, or anything they could supply.
▪ Swimming pool/water park
▪ Create some zoning for light manufacturing and commercial
▪ Secure water supply to allow more development
Services
▪ Access to a medical doctor in town
▪ Daycare centre
▪ Library/office equipment for public use
▪ Long-term seniors complex (full care facility offering condo style rooms and suites for the aged)
▪ A real credit union that provides business loans and financial services; KCU merger/takeover was not good for Edgewater!
▪ Create a directory of local services. "buy local"

Marketing
▪ Advertising
▪ Sell the location - away from the craziness of Invermere and Radium
▪ Develop the market concept
▪ Fundraisers - sell shares
Nature/ Environment
▪ Hiking, biking, bird watching etc
▪ Focus/emphasis on the wetlands/'green' spaces/environmentally sound activities
▪ More active outdoor tourism
▪ A research centre on the Great Columbia wetlands - science on the plants, animals, hydrological systems, geology, meteorology, and natural history: Liaison with universities to set up studies in all these areas – conservation
Entertainment/ Culture
▪ Music festival similar to Woodstock every year
▪ Have "Edgewater Days "
Other
▪ Why does it need to be economically self-sufficient?
▪ Community being welcome in the Valleys Edge Resort

7. Can you suggest any other ways for improving Edgewater?

Infrastructure
▪ Pave some streets, they are terrible in the whole town
▪ More trees & flowers
▪ Outdoor washrooms in the park.
▪ Clean-up vacant lots & force those whose places are an eye sore to clean them up
▪ New Main Street with boulevards and side walks instead of ditches.
▪ Sidewalks on Main Street
▪ 4 way stop at the main junction
▪ Repair the roads-they're a disgrace-more welcoming entrance
▪ Demolish old buildings across from the hall. They are an eyesore. This would be an ideal location for a business.
▪ Round-about at Columbia & Selkirk
▪ Fix roads/add flower boxes maintained by a contractor

▪ Clean-up Main street i.e. The old buildings ▪ This town is in need of a major community clean-up. Let's get rid of the rusty old cars & machinery and old wood & garbage. ▪ Reduce speed on highway to 80 km/h like Parson etc. ▪ Repave roads ▪ Image: New highway sign ▪ Entrance sign on the highway has been allowed to disintegrate - looks shabby and run down ▪ New signage at highway entrances ▪ Attractive signage on highway – 'Edgewater 1 km' & 'Edgewater' ▪ We could use a nice campground or motel or a few small cabins together with a small pub/restaurant
Services
▪ Indoor recreation facilities ▪ Install an ATM machine. ▪ Encourage more involvement in the Rec. Society. ▪ Low income senior housing/senior housing ex: like Invermere Manor but some 2 bedroom also ▪ I think a water park would be great ▪ Splashpark for children would draw families
Social/ Cultural
▪ Connect with the new and growing young families ▪ Celebrate the 40 year history of the Open Market! It's a genuine cultural achievement ▪ More policing; reduce drunks, quads, & snowmobiles on our streets ▪ Try to find recurring festival/event that could grow & draw tourists in ▪ Curfew ▪ Revised Housing Control - age restriction on mobile homes.
Nature/ Environment
▪ Need bicycle trail to Radium, later also to Brisco ▪ Riverlands Park opening onto River to allow public, non-motorized recreation ▪ Persuade the sawmill to redirect or shield the lights (and possibly the sound) ▪ Get sawmill to build sound barrier to protect community from its excessively loud noises and to shield its yard lights so they don't shine into town ▪ Force the mill to build a sound wall. We can't be quiet ,picturesque place to live with noise happening

8. Do you have a home-based business and/or are self-employed?

No	12
Yes	8
No answer	1

9. List any Edgewater businesses or community services that might benefit from being part of a community hub in a central location like the Post Office area (e.g. renting some space for displaying products, renting a small amount of office space, etc).

Local artisans displaying their work. School probably doesn't have the money, but a small gallery of art & creative projects they are involved in. Let everyone know what our school is up to. Bookkeeper (with shared space - fax machine, copier, etc.)
Accounting- Office services-- Any that respond to this survey See attachment re: cooperative in Edmonton
At the very least, we need an ATM. A co-op office space with copier, printer, scanner, internet, meeting space, display space would be great if local businesses would support it.
Smaller groups like 'Moms & Tots' need an area to rent that is not so big so having open office spaces would be good.
Banking
We need banking / ATM
Artists, jewellery makers, wood carvers, daily fresh market in summer, hair dresser, massage
Daycare, reading centre, hairdresser, bookkeeping, cafe/deli, post office (of course), fitness centre, medical services--drop-in style: dentist, eye, physio, etc
Small business registry could allow all small businesses to rent a space to advertise. Then the locals would call locals.
Library, glass store
1.) Bookkeeper 2.) H& R Block 3.) Office building with rental space
Because Edgewater is off the beaten track retail businesses would be better to do business in Radium where they get more exposure. Running home-based businesses is fine.
A common marketing agency for the local guides and outdoor recreation businesses A trades association to share overhead (like accountancy) and job opportunities, display products.
Premium products people would be willing to visit Edgewater (ice-cream, bakery, restaurant, eco-friendly products). Think McKay's ice cream in Cochrane...people take day-trips from Calgary to go there. A magnet to

attract visitors to our community.

Community Session II - October 13, 2010

The second community meeting was held on October 13, 2010 and was open to the entire community with the purpose of:

- ☐ reviewing the community engagement results (Community Meeting in June, Community Survey, and Stakeholder Interviews),
- ☐ discussing progress on the feasibility of the community hub and,
- ☐ setting some priorities for community improvement based on the feedback from the community engagement.

Thirty people attended this meeting.

Agenda

Introductions, Thank the sponsors, Overview & Objectives of Session (Gerry Wilkie – RDEK Director, Mike Stolte – CIEL)
Update • Project Summary Objectives, Steps • Results of Survey, Community Meeting, Interviews • Key Themes • Next Steps, with community hub concept
Other possible community priorities
Next steps, Check-out & Conclusion

Objectives of Evening

- Inform participants of the project background, progress to date
- Instil a sense of shared responsibility for the economic future of Edgewater
- Be inclusive of all segments and sectors of the community
- Progress/ feedback on hub
- Identify other community initiatives for improving community and economic development's prospects
- Determine support for initiatives; form action committees if possible
- Assist community in moving forward on hub &/or other initiatives

Ideas on Hub

Mike presented those ideas which seemed to have the most community support (determined from the various community engagement mechanisms [key stakeholder interviews, survey, community meeting]).

- Coffee shop/bakery (\$ generating)
- Display windows of local businesses (\$ generating)
- Business directory/photocopier/ trades listing
- ATM
- Tourism centre (with maps, some local history, trailhead, info on local outfitters—possibly volunteered staffing)
- Day care/ mom & tots space
- Pharmacy/medical (one day/week)
- Library/book exchange

After these hub ideas were presented, the community was asked for feedback. The feedback will be incorporated into the feasibility planning going forward.

Next steps on the hub were identified to be:

- Determine ownership (There was support for a community organization managing an RDEK-owned facility. Attendees expressed clearly that any hub must break—even at minimum and not impose additional taxes on residents).
- Outline possible design configurations
- Cost estimates on building construction
- Identify possible anchor tenants

Mike will work with the Advisory Committee to move these forward.

Other Initiatives to Improve Community

Nine community improvement initiatives were then presented (identified through community engagement). Mike commented that there seemed to be passion and community energy around each of these:

1. Identify opportunities around river & trails for tourism &/or community use
2. Strategy for more activities around Community hall, Rink, Ball diamond, Creating a performance centre
3. Tourism strategy for community
4. Suss out agriculture ideas (Co-op, Greenhouse, Root cellar storage, Harvest festival)
5. Creation of a trade association
6. Beautification (Entrance, Roads, Vacant lots, Around park)
7. Festival or special event (e.g. 40 years of Open Market, May Day, Harvest Festival, Other)
8. Signage (Entrance, Around Radium)

9. Welcoming committee (New residents, Recruitment of young families)

Mike spoke to each of these and then asked the participants to add others they thought were worth consideration.

A dotmocracy exercise for setting community priorities (and to form action groups around) was then held in which:

- Everyone was allowed 5 votes
- Votes were based on those initiatives:
 - That best assisted the community
 - Participants, personally, were willing to put some time & energy into

The results in the chart below show the number of votes for each.

<i>Possible Short Term Actions</i> <i>Shaded items were chosen as priorities and became the subject of action groups.</i>	Votes
Beautification (entrance, <u>roads</u> , vacant lots, around park) and Signage ¹ (entrance, around Radium)	14
Coffee Shop, Meeting place concept	13*
Identify opportunities around river & trails for tourism &/or community use	9
Strategy for more activities around community hall, rink, ball diamond, creating a performance centre	8
Tourism strategy for community and economic development committee (include website)	8
Festival or special event (e.g. 40 years of Open Market, May Day, Harvest Festival, Other)	4
Welcoming committee (new residents, recruitment of young families)	4
Volunteer recruitment initiative	3*
Suss out agriculture ideas (co-op, greenhouse, root cellar storage, harvest festival)	2
Creation of a trade association	1

¹ Signage garnered 8 votes and was combined with Beautification (14 votes) as it was acknowledged these two areas had some overlap and possible synergy.

*Actions suggested from the floor.

Moving Forward – Actions Groups & Reality Check

Community members were asked to form action groups around the 3 initiatives that garnered the most votes.

Twenty people joined the 3 community improvement action groups. Each group worked for 20-30 minutes and then reported out to the meeting. (See separate Reality Check reports in Appendices for progress on each of the 3 selected actions)

Conclusion

Mike reiterated that the success of the selected actions and the communities' collective fates themselves is dependent on the energy that the community puts into it. Gerry Wilkie and the Advisory Committee has helped to facilitate the process to date but the action teams and the larger community now needs to ensure actions get carried out to help to build a health economy. Mike also stressed that there are many excellent ideas identified in the surveys and at the November community session (see appendices) which could be viable public or private enterprises.

He concluded the session with several quotes:

- "The future of every community lies in capturing the passion, imagination and resources of its people." - **Ernesto Sirolli**
- "Perhaps the most important resource available to the entrepreneurial community is the personal initiative of the individuals who call it home"
Heartland Center – *"The Entrepreneurial Community -- A Strategic Leadership Approach to Community Survival"*
- "We are the leaders we have been waiting for" - **Hopi Elder**

Gerry Wilkie and the Advisory Committee thanked everyone for attending.

Feasibility Study

Community Hub - Determining Community Uses

At the Oct. 13/10 Advisory Committee meeting and the Community Session (immediately following the AC meeting) Mike laid out the next steps to complete the project. Next steps on the hub were identified to be:

1. Determine ownership. (There was support for a community organization managing an RDEK-owned facility. Attendees expressed clearly that any hub must break—even at minimum and not impose additional taxes on residents).
2. Identify possible anchor tenants. (Determined through a synthesis of inputs from community engagement process. The intent of the process was to identify possible businesses and services that might be tenants in a community hub & determine whether rents generated from these might be sufficient to offset costs – mortgage, operating expenses, etc.)
3. Outline space requirements and possible design configurations (see below)
4. Cost estimates on building construction (see below)



Mike presented those ideas which seemed to have the most community support (determined from the various community engagement mechanisms [key stakeholder interviews, survey, community meeting]) to the Advisory Committee and to the public at the Community Session II (October 13, 2010).

Some of these were community services that did not seem likely to generate an income (to offset rent/mortgage payments) or generate marginal income. Others,

indicated below (see - \$ generating), were seen to have the potential to generate some income.

- Coffee shop/bakery (\$ generating)
- Display windows of local businesses (\$ generating)
- Business centre/ directory/photocopier/ trades listing (\$ generating)
- ATM
- Tourism centre (with maps, some local history, trailhead, info on local outfitters—possibly volunteered staffing)
- Day care/ mom & tots space
- Pharmacy/medical (one day/week)
- Library/book exchange
- Other*

After these hub ideas were presented, the community was asked for feedback. Both the AC and the attendees at the public meeting generally agreed with possible uses and assumptions of space allocations. The feedback was incorporated into the feasibility plans going forward.

* The idea of incorporating affordable housing units above the commercial hub was discussed at the AC. It was thought that somewhere between 2 units (approximately 1700 s.f. each) to 4 units (800-900 s.f. each) could be built at a lower cost than construction costs for ground floor units. There was also discussion involving the possibility of the Columbia Basin Trust or other provincial agencies offsetting costs of these units.



Space Requirements and Probable Rent Generation

NOTE: See assumption notes below table for a detailed explanation

	SPACE REQUIREMENT (s.f.)*			RENTAL INFORMATION		
	Currently	Minimum Needed	Maximum Needed	Quantity	Rent/Unit	TOTAL Rent/Month
1 Post office	250	400	600	1	\$ 125	\$ 125
2 Display Windows for Business	n/a			5	\$ 150	\$ 750
3 Café	n/a	800	1000	1	\$ 1,000	\$ 1,000
4 Library/Resource Centre	600	600	600	1	\$ -	\$ -
5 Day Care	n/a	625	800	1	\$ 800	\$ 800
6 Business Centre/Medical	n/a	500	500	3	\$ 250	\$ 750
7 Medical/Pharmacy (one day/wk)	n/a	0	0	1	\$ -	\$ -
8 ATM	n/a	0	0	1	\$ -	\$ -
9 Tourism Centre	n/a	0	0	1	\$ -	\$ -
		2925	3500			\$ 3,425

* Current post office building is approximately 2,400 sf.

Notes & Assumptions

Notes & Assumptions		
1	Post Office	The current space is inadequate. A slightly larger space would be needed for sorting & storage. The current rent is thought to be the most that can be paid.
2	Display Windows for Businesses	These could surround the post office (e.g. behind glass windows) & be rented out to area businesses to advertise their goods/services. At the first public meeting (June 2010) several businesses suggested they would/could rent spaces if they were to become available. It is assumed there may be 5 businesses renting at \$150 each (estimate of affordability from public meeting – a \$100-200 figure was suggested as affordable by those businesses present). However, there may be a greater demand if all businesses in the Radium/Edgewater area (& possibly Invermere) were canvassed.
3	Cafe	The AC estimated that approximately 800-1000 s.f. of space would be required (1/3 kitchen and 2/3 serving space) based on their knowledge of similar small cafes in other rural communities. The AC also suggested that rent of no more than \$1000/month (not including taxes, utilities, etc.) might be the maximum affordable given the unknown nature of traffic volumes
4	Library/Resource Centre	The current library is more accurately described as a book exchange. It was felt that expanding its offerings so that it could also become a community resource centre would be beneficial. This might include a donated computer with an Internet connection (similar to the federal government's Community Access Program (CAP)). The AC also felt that the centre would complement the café. Some space savings could be achieved in the design (not taken into account in these preliminary space allocations). The current library pays no rent. It is not expected to contribute in any new allocation.
5	Day Care	The AC based this estimate roughly on Radium's day care space. The AC also estimates that the day care could afford between \$625-800/month in rent.
6	Business Centre	This space could house up to 4 businesses requiring 100 s.f. each. It was felt that one room with walls would be of greatest benefit as it could serve as a meeting room and possibly provide a private space for meetings when necessary. Through the community process, several people suggested this space might serve a bookkeeper and several other home-based businesses that might want to have the benefits of shared space, equipment (e.g. photocopier, fax, etc) and camaraderie – a mini incubator of sorts. The AC estimated that \$250/month for a shared space was reasonable with a maximum of 4 spaces available.
7	Medical/Pharmacy	The community engagement clearly indicated that a physician, pharmacist and other medical services would be highly desirable. While it is unlikely to have a full-time service available in the community, Edgewater might be able to acquire a part-time (e.g. one day /week) visit from various medical practitioners. It was assumed that this space could be incorporated into the business centre. This might generate some revenue although it was assumed to be cost neutral.
8	ATM	Although the community lost the services of Kootenay Savings Credit Union by virtue of its relocation to Radium, it was felt that an ATM in Edgewater would have substantial benefit. It is assumed to be revenue neutral and to require minimal space.
9	Tourism Centre/Trailhead	The community engagement process indicated that tourism would be the key economic driver in the area. It also indicated that the river and trails in and around Edgewater were the community's most under-utilized assets. While it is unlikely that a staffed tourism centre could acquire funding, it was felt that an unstaffed map centre/trailhead at the hub would be of benefit to the community

		and area. This could be located on an outer or inner wall taking up little of no space. It is unlikely to generate revenue. (During the summer months, the trailhead could be staffed by a volunteer or a summer student giving greater benefit to the community and area's tourism-related businesses.)
10	Other	Arts and crafts and other local wares could be displayed in the hub, specifically in the business centre, the resource centre or in the café. This would not be expected to generate significant revenue. However, this would provide an outlet for local artists and artisans and generate some economic activity for the community. In terms of affordable housing units, the AC suggested that 2nd floor construction for housing above the hub would cost approximately 65% - 75% of main floor construction. With a construction subsidy, there was some feeling that this might turn a marginally feasible project into a feasible one. Subsequent to the community meeting, discussions were held with CBT (Aimee Ambrosone) and the BC Non-Profit Housing Society (Karen Cooper). There are no standard programs to offset subsidized housing on a per unit or sf basis. In addition, studies demonstrating demand would have to be generated.

Feasibility Considerations

Construction Costs

Commercial construction costs differ considerably based on the type of construction and the intended use.

The consultant based feasibility on a \$300 /s.f. construction cost assumption. This is based on estimates from Diane Sirois, Sr. Commercial Lender at Kootenay Savings Credit Union (KSCU). This is slightly lower than average commercial construction costs in the East Kootenay over the last few years, and factors in a somewhat slower economy. Prefab commercial construction could be completed at much lower rates.

3500 s.f. (estimated need for space) x \$300 per s.f. = \$1,050,000

Estimated operating costs

\$4 /s.f. x 3500 s.f. = \$14,000/yr (\$1,167/month)

Based on estimate from Scott Veitch, Senior Commercial Realtor for Century 21 Creston made up of:

- ☐ \$1 /s.f. light
- ☐ \$1 /s.f. heat
- ☐ \$1 /s.f. taxes
- ☐ \$1 /s.f. insurance

Estimated Down Payment

☐ \$100,000

Based on sale of 2 commercial lots across street (owned by RDEK). Estimate of value by Gerry Wilkie.

Mortgage

Although the RDEK owns the property and would need to go through a different process for financing the construction of this building, we have assumed the costs and mortgage process to be that of a more traditional commercial lending process to a private developer. In this way, we can determine whether the project is feasible from a market perspective.

- ☐ \$950,000, 15 year amortization (maximum for commercial buildings), 5 year term, 5.29% (based on TD Canada Trust rate at Oct. 29/10 for 5 year closed on residential mortgage [it is most likely a commercial rate would be slightly higher])
- ☐ \$7,628/ month

Total Costs vs Possible Rents Generated

	Monthly
Mortgage	\$7,628
Operating Costs	\$1,167
TOTAL	\$8,795
Total Possible Rent	\$3,425
Surplus/(Shortfall)	(\$5,370)

Conclusion

This project would **not** be feasible given the current conditions and assumptions for revenues and costs.

Options

Options	Explanation	Action
1. Construct replacement facility to meet community needs as expressed through community engagement process (as per feasibility study outlined above)	This option is too expensive given the potential for covering mortgage and expenses.	No action.
2. Do nothing	Building will continue to deteriorate	The action (or inaction) is not viable over long term.
3. Look at lower cost options for construction.	With the post office generating minimal rent (and indicating they are unable to pay for more), it is unlikely that a cost-effective solution will be found. However, looking at a prefab arrangement might reduce mortgage by half or more, bringing the project closer to feasibility. In addition, volunteer labour – e.g. a barn raising - has been used successfully in the community in the past for projects like the refurbishment of the community hall.	Further exploration required
4. Seek out commercial operator to construct.	It is extremely unlikely a commercial operator would construct a building to house such low rent generating activities.	No action.
5. Look at other creative ways of providing services.	Other community assets – old KSCU location, community hall - could serve some uses identified through the community engagement. For example, the KSCU building could possibly be brought up to acceptable standards for a community meeting spot/ coffee house through a combination of community volunteer labour and donated materials.	Further exploration required.
6. Explore feasibility of cost-effectively maintaining & improving building	Inspection and assessment required.	Further exploration required.

Appendix B

**Edgewater Redevelopment Planning Committee
Community Update**
March 2022

COMMUNITY UPDATE

MARCH 2022

Hello Edgewater Residents,

I would like to give you an update about the work of the **Edgewater Redevelopment Planning Committee**.

As many of you know, there is an effort underway to consider possibilities for future redevelopment of the Post Office and former Credit Union buildings as well as the vacant lots kitty-corner to Pip's Country Store. While the properties are owned by the RDEK, as your Electoral Area Director, I want to make it clear that any redevelopment would only occur after full community consultation and formal assent.



In October 2021, about 50 residents attended a public meeting at the Community Centre and voiced their ideas, concerns and questions. You may recall receiving minutes from that meeting via the RDEK distribution list. If not, please consider signing up to receive emails with Edgewater news, including updates about this process here: https://www.rdek.bc.ca/about/email_group_sign_up.

At the October meeting, about 12 residents volunteered to form an Edgewater Redevelopment Planning Committee. We have been joined by Gerri Brightwell, Manager with BC's Regional Economic Development Branch for our region, and have also enjoyed hands-on support from the Columbia Valley Chamber of Commerce.

The committee has been meeting monthly and is looking into the opportunities and implications of several possible concepts for these properties. We are looking for practical solutions, including funding opportunities, partnership options and ways of implementing and managing projects in communities such as ours. The options on the table range from trying to maintain the status quo with small scale changes, to more comprehensive options possibly involving commercial or other partners.

The committee is developing an evaluation system to narrow down the ideas and options that have taken shape. Our goal for the coming months is to:

- a) answer the questions the community posed at past meetings and since; and,
- b) to reach a point where we can invite you to share what we have learned and to present some options for the future of the properties in the centre of Edgewater.

Should you wish to provide input, or get answers to any burning questions, I encourage you to contact me by email at director.wilkie@rdek.bc.ca or by phone at (250) 347-9841, or simply talk to me when I see you around town. Your thoughts are likely on other residents' minds as well, and it would be helpful for myself, and the committee to receive them.

Thank you for your patience as we work through this exciting and challenging process. We hope for your support and trust as we move along, and look forward to your participation in future stages of this process.



A handwritten signature in black ink that reads "G. Wilkie".

Gerry Wilkie
RDEK Electoral Area G Director

Appendix C

Edgewater Open House – Presentation Panels
February 2024

WELCOME

The Edgewater Community Hub Open House is intended to present concepts for the incremental development of two community-owned properties in the core of Edgewater. These concepts were developed by a community committee over two years.

**Please review the information and ask questions.
We welcome your feedback and seek your endorsement of this vision for an 'Edgewater Hub' and the opportunities it presents for our community.**

The Edgewater Community Hub is an initiative of the



with funding from



OBJECTIVES OF THE REDEVELOPMENT PLAN

The objectives of this redevelopment plan are:

Economic Vitality – to stimulate local economic activity by providing commercial space that accommodates a local Canada Post outlet and additional commercial / retail opportunities as may become viable in the future with the goal of providing services to residents in the local community.

Community Enhancement – to create a welcoming and inclusive space that enhances community interaction and offers amenities and while tying into and supporting the neighbouring community greenspace and community hall.

Sustainability – to implement sustainable design and construction practices reducing the environmental footprint and operating costs of the development in accordance with the Regional District's requirements for energy efficiency.

Mixed-Use Integration – To integrate commercial and residential uses, promoting a live – work – play environment while providing some attainable housing to residents of the community.



DEVELOPMENT PROPERTIES


Vermillion Property

The Vermillion property is a vacant parcel located at the intersection of Selkirk Avenue and Vermillion Street and comprises a total area of 836m² (9,000ft²) or about 0.21 acre. The Vermillion property is currently zoned R-1 for residential uses.

Post Office Property

The Post Office property is located at the intersection of Selkirk Avenue and Sinclair Street and comprises a total area of 1198m² (12,900ft²) or about 0.30 acre.

The property includes the Edgewater Post Office and the old credit union building. The old credit union building has been deemed unfit for continued use and must be demolished. The current post office has significant structural issues and is proposed to be demolished. The Post Office property is currently zoned C-1 for commercial uses.



DEVELOPMENT PROGRAM

The development program for the properties has been established based on the findings of the 2010 Centre for Innovation and Entrepreneurial Leadership (CIEL) report “Working Towards a Sustainable Economy in Edgewater, Community Engagement Report, Feasibility Study for Community Hub Report” as well as community input from the 2021 townhall meeting and direction from the Edgewater Redevelopment Planning Committee.

Vermillion Property

The Vermillion property is proposed for development of a daycare facility. The daycare proposed is envisioned for approximately 30 children.

Post Office Property

Proposed mixed-use development of the Post Office property will include:

Post Office - The post office is proposed to be approximately 110m² (1200 ft²) and will be located on the ground floor of a building with access from Selkirk Avenue. A minimum of four (4) parking stalls and one loading stall are required for the post office.

Commercial - Retail Unit - The commercial retail unit proposed is to be approximately 100m² (1076ft²) and will be located on the ground floor of a building with access from Selkirk Avenue. Three (3) parking stalls are required.

Attainable Non-Market Housing - A total of 534m² (5,748 ft²) of attainable non-market rental units are proposed which represent 3 two-bedroom apartment style units and 3 three-bedroom townhouse style units. Nine (9) parking stalls are required for this use.

Public Gathering Space - Public outdoor space for community gathering and events is proposed with visual and physical connection to existing park to west of the property.

Streetscape Improvements

Sidewalks and walking paths connecting the post office property, park, community centre, store, child care and other businesses in the community core area.

EDGEWATER Community Hub

BUILDING FORM & CHARACTER

Building forms for both the Post Office Property and the Vermillion Property should recognize site patterns and help define entries to interior courtyards, building entrances, public spaces and enhance the pedestrian scale.

The building form utilized for the Edgewater Community Hub has been chosen to build upon Edgewater's agricultural heritage while meeting modern building code and design requirements. The proposed architectural style utilizes elements of rural agrarian building forms combined with modern building materials to ensure buildings that fit within the fabric of the community. Low maintenance building materials – such as cementitious siding (Hardi-plank) and metal roofs reduce operating costs for the development.

The photos shown below are intended to capture the scale of development and simple detailing proposed while utilizing building form to create a pedestrian friendly environment to encourage community gathering.



BUILDING FORM & CHARACTER


Vermillion Property

The development program for the day care facility on the Vermillion property is implemented in a single-storey building of approximately 222m² (2,390 ft²). This building is supported by an outdoor space of not less than 180m² (1,938 ft²) plus allocation for parking, sidewalks, non-accessible space (ie. mechanical area), and other considerations.

Simplified building section-elevations have been developed to illustrate building massing and layout for the child care facility.




Conceptual South Section / Elevation



Conceptual East Section / Elevation



Conceptual South Elevation



Conceptual East Elevation

BUILDING FORM & CHARACTER

Post Office Property

The main floor of the north building includes the post office (110m², 1184ft²) and the commercial retail unit (100m², 1076ft²). The second floor of the north building includes three (3) – 2 bedroom rental residential units. Each unit is 67m² (721ft²) in accordance with BC Housing requirements. The units are accessed from an exterior stair (which could also be enclosed).

The south building comprises three (3) – 3 bedroom rental residential units. Each unit is 111m² (1195ft²) (55.5 m² per floor) in accordance with BC Housing.


Conceptual floor plans and simplified building elevations have been developed to illustrate building massing and layout for the Post Office Property.



*Conceptual North Elevation
Main Floor - Post Office and Commercial Retail Unit
Second Floor - Attainable Non-Market Housing*



*Conceptual East Elevation (View from Park)
Post Office and Commercial Retail Unit and Attainable
Non-Market Housing with Public Interior Courtyard*




Conceptual Floor Plans - Main Floor Plan (left) and Upper Floor Plans (right)

SITE PLANS

Vermillion Property

The site plan for the Vermillion property considers the proposed child care building program, including requirement for outdoor space, required setbacks from property lines, parking and drop-off requirements, among other considerations.

The site plans developed for this property are constrained by required parking and property setbacks. The property setbacks within the P-1 (Public Institutional) zone require a front yard setback of 7.5m (24.6ft) along Selkirk Avenue and rear and side yard setbacks of 4.5m (14.8ft).




SITE PLANS

Vermillion Property

OPTION 1 (previous panel) - Option 1 locates the child care facility forward on the lot with the outdoor play area located at the rear of the lot. Parking is located off of Selkirk Avenue.

OPTION 2 (this panel) - Option 2 moves the child care facility to the back of the lot with the outdoor play area located at the front of the lot. Parking is located off of the lane behind the building.




SITE PLAN

Post Office Property

The site plan developed for the Post Office property places the post office and commercial retail unit facing Selkirk Avenue to maximize exposure to the street. Parking stalls are provided from Selkirk Avenue for these uses.

Three 2-bedroom units are provided above the post office and commercial retail unit with access from the courtyard. The south building is configured to wrap around the corner of the site and create a partially enclosed courtyard. Three 3-bedroom townhouse units (2 storey) are provided in the south building.

A courtyard area is created by the building forms which creates opportunities for public gathering. The courtyard is envisioned to provide casual space for local residents to meet and interact while also functioning as an extension of the park for organized events.



CONSTRUCTION BUDGET

Vermillion Property

Development of the Vermillion property as a child care facility will involve site servicing, construction of the child care building, building FFE (fixtures, furniture and equipment), and construction of outdoor spaces including parking and outdoor child care facilities as summarized below:

Description	Area	Unit Cost	Units	Cost
Land Use Approvals (Zoning)		\$ 10,000	allowance	\$ 10,000
Legal and Subdivision		\$ 10,000	allowance	\$ 10,000
Geotechnical Review		\$ 15,000	allowance	\$ 15,000
Environmental Assessment		\$ 10,000	allowance	\$ 10,000
Site Works	836 m ²		allowance	\$ 10,000
Site Servicing (Water / Sewer)			allowance	\$ 20,000
Development Charges			allowance	\$ 15,000
Building Construction	222 m ²	\$ 4,000	per square meter	\$ 888,000
Furniture, Fixtures & Equipment	222 m ²	\$ 250	per square meter	\$ 55,500
Landscaping and Other Works			allowance	\$ 75,000
SUB-TOTAL				\$ 1,108,500
Professional Fees (15%)			percentage	\$ 166,275
Contingency (20%)			percentage	\$ 221,700
TOTAL				\$ 1,496,475

CONSTRUCTION BUDGET

Post Office Property

Development of the Post Office property with a new post office, commercial / retail unit and attainable non-market housing will involve site servicing, construction of the commercial and residential buildings, building FFE (fixtures, furniture and equipment), and construction of outdoor spaces including parking and community gathering area as summarized below

Description	Area	Unit Cost	Units	Cost
<i>Land Use Approvals (Zoning)</i>		\$ 10,000	<i>allowance</i>	\$ 10,000
<i>Legal and Subdivision</i>		\$ 10,000	<i>allowance</i>	\$ 10,000
<i>Environmental Assessment</i>		\$ 10,000	<i>allowance</i>	\$ 10,000
<i>Geotechnical Assessment</i>		\$ 15,000	<i>allowance</i>	\$ 15,000
<i>Demolition and Remediation</i>		\$ 60,000	<i>allowance</i>	\$ 60,000
<i>Site Works</i>			<i>allowance</i>	\$ 10,000
<i>Site Servicing (Water / Sewer)</i>			<i>allowance</i>	\$ 30,000
<i>Development Charges</i>			<i>allowance</i>	\$ 15,000
<i>Building Construction (Commercial)</i>	210 m ²	\$ 3,500	<i>per square meter</i>	\$ 735,000
<i>Building Construction (Residential)</i>	201 m ²	\$ 3,250	<i>per square meter</i>	\$ 653,250
<i>Building Construction (Residential)</i>	336 m ²	\$ 3,500	<i>per square meter</i>	\$ 1,176,000
<i>Furniture, Fixtures & Equipment</i>		\$ 100,000	<i>allowance</i>	\$ 100,000
<i>Parking Lot and Driveways</i>			<i>allowance</i>	\$ 35,000
<i>Landscaping and Other Works</i>			<i>allowance</i>	\$ 200,000
SUB-TOTAL				\$ 3,059,250
<i>Professional Fees (10%)</i>			<i>percentage</i>	\$ 305,925
<i>Contingency (20%)</i>			<i>percentage</i>	\$ 611,850
TOTAL				\$ 3,977,025

DEVELOPMENT PHASING

Post Office Property

Phasing development of the Post Office property may be considered based on funding availability.

Optimally, the new post office / commercial retail building would proceed as phase one of development thereby replacing the existing post office building and maintaining this service in the community.

Another option would be to simply proceed with the post office building. If this option is proposed, it is recommended that the building be situated as envisioned in the site plan to ensure suitable area is preserved for future development of the commercial / retail space and non-market rental accommodation.



Conceptual North Elevation (above) and East Elevation (below) of Stand-alone Post Office



Post Office Property - Site Plan - Potential Phasing Option

CONSTRUCTION BUDGET

Post Office Property

The community may also consider development of a stand-alone post office on the Post Office property as the first phase of a multi-year redevelopment of the property.

Development of a stand-alone post office would require site servicing, construction of the post office building, building FFE (fixtures, furniture and equipment), and parking as summarized below:

Description	Area	Unit Cost	Units	Cost
Land Use Approvals (Zoning)		\$10,000	allowance	\$ 10,000
Legal and Subdivision		\$10,000	allowance	\$ 10,000
Environmental Assessment		\$10,000	allowance	\$ 10,000
Geotechnical Assessment		\$15,000	allowance	\$ 15,000
Demolition and Remediation		\$60,000	allowance	\$ 60,000
Site Works		\$10,000	allowance	\$ 10,000
Site Servicing (Water / Sewer)		\$15,000	allowance	\$ 15,000
Development Charges		\$5,000	allowance	\$ 5,000
Building Construction (Commercial)	110	\$3,500	per square meter	\$ 385,000
Furniture, Fixtures & Equipment		\$25,000	allowance	\$ 25,000
Parking Lot and Driveways		\$25,000	allowance	\$ 25,000
Landscaping and Other Works		\$25,000	allowance	\$ 25,000
SUB-TOTAL				\$ 595,000
Professional Fees (15%)		15%	percentage	\$ 89,250
Contingency (20%)		20%	percentage	\$ 119,000
TOTAL				\$ 803,500

FREQUENTLY ASKED QUESTIONS

CANADA POST

Q: Can we fix up the old post office?

A: No, the existing building is not structurally sound and is beyond repair. A structural engineer has recommended demolition of the building.

Q: Does Canada Post have anything to do with the building?

A: No, the existing building is owned by Regional District of East Kootenay. Canada Post pays the contractor that operates the facility.

Q: How do we know Canada Post will maintain a location in Edgewater after we build a new building?

A: Canada Post has indicated that it wants to maintain an Edgewater location. Loss of the Edgewater facility would put too much pressure on the Radium post office.

Q: How will postal service be maintained while a new building is constructed?

A: A temporary facility will be required while the new facility is being constructed. The specifics of how this will be achieved still need to be worked out.

CHILD CARE FACILITY

Q: How do we know a child care facility is even needed?

A: The Eva Joseph Learning and Cultural Society and Little Badgers Early Learning Centre commissioned a study to provide a snapshot of the current state of child care for the Columbia Valley region. The study, "Columbia Valley Child Care Snapshot" concluded that there is presently only a 19% child care coverage rate observed in the Columbia Valley – categorizing the community as a child care desert. It is recommended increasing the coverage rate in the community to 80% for ages 0 to 3 years, 70% for ages 3 to 5 years, and 55% for ages 6 to 12 to adequately service the community's child care needs. In order to meet these targets, an increase of 606 child care spaces (for a total of 857 licensed spaces) is needed – an additional 138 spaces for under age 3 years, 118 spaces for ages 3 to 5 years and 350 spaces for ages 6 to 12 years.

Q: Who will operate the child care facility?

A: Part of the due diligence required prior to commencing construction of a new facility will be to secure an operator. The committee is aware of potential operators in the area that have expressed interest.

ATTAINABLE HOUSING UNITS

Q: Will attainable housing units be sold?

A: No. Attainable housing units are intended to provide long-term rental housing.

Q: Who will be eligible to rent attainable housing units?

A: The criteria for rental of the attainable units will be confirmed based on local requirements, either based on social need or to provide attainable housing for persons employed in the local area.

FREQUENTLY ASKED QUESTIONS

FUNDING

Q: Where is the money for these projects coming from?

A: Funding for the projects will be from multiple sources. Potential sources of funding include:

- BC Ministry of Housing
- BC Ministry of Jobs, Economic Development and Innovation
- BC Ministry of Education and Child Care - New Spaces Fund
- Columbia Basin Trust
- Regional District of East Kootenay
- rental income for the attainable housing units, post office and retail /commercial space
- taxation revenue

Q: What community partners will be expected to provide input into development and construction of the project?

A: A number of community partners have already provided assistance to the committee and we expect will continue to be involved. These include:

- Regional District of East Kootenay
- Columbia Basin Trust
- Columbia Valley Chamber of Commerce
- Family Dynamix
- Columbia Valley Housing Society
- Rocky Mountain School District #6
- Local child care providers
- BC Ministry of Education and Child Care
- BC Ministry of Jobs, Economic Development and Innovation
- Local consultants and contractors including engineers, architects and builders



Ministry of
Education and
Child Care



Ministry of
Housing



Ministry of
Jobs, Economic Development
and Innovation

FREQUENTLY ASKED QUESTIONS

OWNERSHIP & OPERATION

Q: Who will own the new post office, attainable housing units and child care facility?

A: This concept envisions that the properties will continue to be community owned. The Regional District of East Kootenay (RDEK) will likely enter into long-term lease with community partners for development of the housing component of the project.

Q: Who will operate the new buildings when constructed?

A: The RDEK will likely enter into an agreement with local non-profit groups to operate the new facilities. This may include Family Dynamix or the Columbia Valley Housing Society to maintain and operate the attainable housing units on behalf of the RDEK.

Q: Who will manage construction of the new buildings?

A: The RDEK will likely engage a professional project manager to oversee construction of the new facilities. This will be confirmed as the scope of construction is finalized.

NEXT STEPS

The next steps for development of the Edgewater Community Hub depend on the outcome of this open house and gauging support for the project.

If the community supports the concepts presented here, these are the next steps:

- The RDEK Board must prioritize the project and assign staff to the project.
- The properties must be subdivided (consolidated) and rezoned to permit the proposed uses.
- Further community engagement as part of the rezoning process and to approve funding through taxation, as needed to meet RDEK policy requirements.
- Partnerships with local non-profit groups must be confirmed for operation of the child care and attainable housing.
- Ownership options for the new buildings must be confirmed with the RDEK.
- Funding from Provincial and local government and other sources must be secured.
- Project manager must be engaged by the RDEK.
- Detailed design of the facilities must be completed.
- Options for temporary post office explored.
- Service area for funding project must be created by RDEK.

Appendix D

Edgewater Open House – Comments Summary
February 2024

OPEN HOUSE FEEDBACK AND COMMENTS

February 6, 2024

Summary of Comments Forms Completed at Open House

Recommend a phased approach to start with demolition of buildings, then post office building, then daycare, then attainable housing.

Does commercial space include facilities for restaurant / café?

Concern over tax increase.

Concern about viability of a business in commercial space.

Concern about maintenance of attainable housing. I understand there is a need for it, however property maintenance and upkeep remain a concern for the appeal of the hub.

Love the concept.

- Post Office
- Childcare
- Rental

Establishes Edgewater community.

Concern

- Low-income housing comes with risk.
 - Long term plan to keep condition of building.
-

Post office building – rebuild overdue, even if full concept with rental units does not go through new safe building is much needed.

Concern would be ensuring long term operation of daycare facility and ensuring building could function, be used if daycare closed and was not able to operate.

Concerns over low-income housing and management of the site to prevent abuse of housing and risk of increase of theft or drug use in community. In communities that have completed projects including low-income housing in the past usually don't add services such as RCMP or ambulance and fire to support potential problems. I would rather see apartments or townhomes sold as residences. A commercial lease may also be a good solution. Daycare and post office ideas look great.

EDGEWATER

Community Hub

I think the open house and display panels were great! Also, the people involved did a great job of coming up with the proposed development.

I think option one for the day care with parking off the street and an outside play area at the back is the best option.

Very pleased with the display.

Very pleased with the concept.

Wonder about housing upper levels – need elevator especially for older, disabled, family's groceries etc.

I very much appreciate the attention to integrating the new building look into Edgewater Community look and feel. I would love for the Vermillion lot to be a park space, but I do understand childcare is needed. A location off main street would be my choice in a perfect world for that project, but I am sure the structure and future use of the lot will be done well and all awareness for safety will be highly considered. Will look forward to change!

The post office is the most important to go ahead with and that cost is acceptable. Commercial space with it depends on cost economy and interest to pay reasonable rent.

The rental units are a whole different kettle of fish – the cost is a lot and maintenance etc. is going to be something else. If it was going to be senior (handicapped etc.) you might have a point, but it is also very expensive and hard to maintain – for example Family Dynamic housing in Invermere is not good.

Daycare – if there are enough kids and parents willing to maintain and pay for it – great- gov't funding is pretty good for that now!

Both my wife and I fully support and encourage the idea of the daycare childcare facility. If the post office building goes ahead then the adjoining building should also be built at the same time in order to reduce construction costs of building a separate building afterward.

I don't believe that the RDEK should be funding the construction of rental housing facilities. Who would decide who is eligible to rent the units, who maintains the quality of the buildings thus preventing major costs of repairs or renos from rental damage.

Maybe the property for the housing rentals could be sold to a developer on the condition that attainable housing would be made available. Thus, saving us the tax paying base from having to carry the significant costs of construction, maintenance, etc.

Love the market look!

Post office standalone is great. Doable for taxpayers.

What about a bit bigger space in the same building as the post office for a small coffee shop?

There is no mention of what the payback is for this project (how many years to pay for this)?

Affordable housing is one thing but how cost rentals managed by the local support groups for drug and alcohol users is not the answer.

How many years will we have increased taxes to pay for this and what is the expected dollar per house in Edgewater to pay for this?

What is the projected revenue vs expenses per year to be?

Focus on getting the post office done and table the rest. I don't see people driving to Edgewater for daycare if they live out of town. The housing would be limited to non-seniors due to the stairs only access.

I feel the top priority should be the post office. The building is in dire need of repairs and expansion, outlets, appropriate lighting, and heating.

Do we need a daycare facility that large?

Will we have potential kids and daycare workers?

Maybe funding for a smaller facility at a later date.

Great idea for more town rentals, however, to be above the post office? That would limit people that are elderly or with physical limitations.

I believe the daycare is a great idea.

I also believe and like the idea of the new post office and retail space, however I am unsure of the rental units above. The cost of building would be my main concern.

I love this project! These buildings will improve the overall impression of our Mainstreet. The project addresses major community issues that if we can have a funding model that mitigates major tax increases would serve the community well. I don't have children but would fully support proper childcare center, to continue to attract young families. I love the idea of attainable housing and if this is something we can make happen as a community I am all for it! Thank you for this detailed presentation and all the work of the past three years that went into putting it together!

I feel that the taxpayer should not be involved in supplying commercial space or housing. Lands owned by the RDEK could be made available to private enterprise.

Fantastic ideas! I love this community, the rentals, daycare, and all hub concepts, greatly needed. Let me know how it goes in the next steps. I would be interested in the style decisions if we tune that with cost.

It's great that we keep our post office! Obviously, our taxes will skyrocket with the whole housing and retail plans etc.
Maybe start with a stand alone post office only and I don't think we need a sidewalk.

A very detailed presentation, good planning. Much needed improvements in the community. Rental units good, with proper supervision and rules.

Daycare is much needed. Good advice for location. My vote would be option one with a play area at the back. Passing traffic should not be able to view the children.

How would this affect our property tax? Is this only taxable in the "fire district" so taxes split over how many properties?

Glad to see the post office would be first phase. Housing, retail, and daycare are all very good ideas.

Still no timelines? Phased development -us- all - together development - not sure what to suggest. The disruption should be minimized if possible, so the mess of construction doesn't consume the town for years. We have a charming functional community, and it would be good if that could be somehow respected while this project unfolds. I think the consideration of a post office (as opposed to rural boxes) for the town of Edgewater is actually much more of a priority than the issue of putting too much stress on the Radium Post Office!

Disappointed that some local services were not included with the layout of the building. i.e. Resource Center / Library Depot where Invermere library could have books available for people who can't travel far.

Like the post office plan as well.

If a daycare must happen, parking space would be better located off the back alley or lane for calmer loading and unloading of children away from traffic and no backing out of spaces into traffic.

Looks good, we both like the idea. Keep it rustic! Thank you everyone who is involved.

I love it! Great concept with a vision for the needs of this community. I really hope it can happen as imagined. Daycare and affordable housing are so needed here. Thank you for all the work on this so far and best of luck with it! Can't wait to see construction begin.

Our preferences for development of the property on the corner of Vermillion and Selkirk that is currently three narrow residential lots.

- Leave as a park.
- Single family Housing
- Daycare with parking off the lane. Parking off Selkirk would be busy and potentially dangerous. We have watched vehicles ripping past Pip's and our house at 50km/h coming out of the playground zone.

Would like to see the speed limit reduced in front of Pip's regardless of weather the Daycare is built on the empty lot.

Please make sure to keep the post office.

Nine units in that space seems cramped.

Opposed to subsidized rental units altogether.

Was hoping for more commercial opportunities for a café for example.

Great presentation and format.

It would be a good exercise to create a 5-10-year plan through potential cost revenue (maintenance, insurance, etc.) The concern would be that the upkeep and inflation of the project would continue to become more burdensome overtime.

Love the keep the post office.

High need rentals for sure.

Daycare is a fantastic idea.

High speed internet would be nice.

Possible store front rentals.

The two buildings with housing are a large financial commitment. Will our taxes be increased?

I will be attending the next public input meeting to learn more and to gauge the opinion of other residents.

Overall, nicely done!

Could use architectural references from:

- Edgewater Colonial - Compare Headquarters across from Pip's - Senator Planta's - Mrs J Langs
- Edward Barfberger - Skilled master stone mason and carpenter
i.e. Frank Thompsons old Place - 3rd on right E of Post Office

No Library, Resource Center, or Café.

Accommodation welcome - not all needs to be two to three bedrooms.

Disposal of hazardous waste - more expensive than quotes.

solving sawdust - fill settlement problem under Fire Hall - refill or excavate.

Good Effort!

Concerned with the speed in which this project will progress...especially with how the current post office building is falling apart.

Glad to see some housing added to the equation.

We would like to see a new post office and daycare. I don't believe we need any rental units or retail. This just opens an area of:

- Who gets them (favoritism)
- Who would oversee the rules, cleanliness, appearance of these rentals?

We don't feel the size of Edgewater would sustain coffee shops and retail shops. The hall should be used more for community socialization.

Summary of Comments Forms Completed at Open House

This is exciting looking at the potential of our little downtown center.

I think the daycare is an excellent & high necessary idea! I think parking on Selkirk makes sense, the back-alley side would be cramped and messy. They may want to talk to Dept of Highways to make it a 4 way stop there though....

I love both ideas for the post office area especially the courtyard and potential areas for business opportunities. However, Im concerned how much taxes would increase. It would be fabulous to go with #1 but #2 may be the route to go leaving the credit union site with potential for the future and extra parking for now....

Also, a public washroom would be lovely for park users. Its almost every time we go to the park occurrence that we either cut our trip short and go home or go to Pips (or outside 😬) and its not just us. I know we use the rink one quite often when we are even out for a walk too.

Thanks for those slides. I love the vision for the two locations and hope the Edgewater community feels the same way. For all these great projects to come to fruition the vision and support of the community is the vital first step, so hopefully your session last week got everyone excited and ready to support you on the journey.

Just had a first review of proposed Edgewater Hub development. First impressions are positive. Wishing I heard the presentation and dialog. Well done! Onward! Bowen Island has a very nice hub, actually 2 of them and one of the photos of building concepts (Redish coloured buildings) look to be from Bowen Island.

Appendix E

RDEK Upper Columbia Valley Zoning Bylaw

4.3 Single Family Residential: R-1

- (1) Principal Uses
 - (a) *Single family dwelling*
- (2) Accessory Uses
 - (a) *Home based business*
 - (b) *Secondary suite*, excluding the original Panorama Mountain Village single family subdivision as shown outlined in black in Figure 2 below:



Figure 2: Original Panorama Mountain Village Single Family Subdivision

- (c) *Backyard chickens*
 - (d) *Backyard beekeeping*
 - (e) *Uses, buildings, and structures accessory to a permitted use*
- (3) Parcel Area

Subject to section 2 of Schedule A to this Bylaw, no *parcel* shall be created in the R-1 zone which is less than 555 m² in area.
- (4) Regulations

In the R-1 zone, no *building* or *structure* may be constructed or placed which contravenes the regulations contained in the table below. Column 1 identifies the matter to be regulated. Column 2 establishes the regulations.

COLUMN 1	COLUMN 2
(a) Maximum density: ▪ <i>single family dwelling</i>	one
(b) Minimum setbacks:	
(i) <i>Principal buildings and structures</i> from:	
▪ <i>front parcel line</i>	7.5 m
▪ <i>rear parcel line</i>	6.0 m
▪ <i>side parcel line</i>	1.5 m
▪ <i>side parcel line</i> adjacent to a <i>highway</i> other than a <i>lane</i>	4.5 m
(ii) <i>Accessory buildings and structures</i> from:	
▪ <i>front parcel line</i>	7.5 m
▪ <i>rear parcel line</i>	1.5 m
▪ <i>rear parcel line</i> adjacent to a <i>highway</i> other than a <i>lane</i>	4.5 m
▪ <i>side parcel line</i>	1.5 m
▪ <i>side parcel line</i> adjacent to a <i>highway</i> other than a <i>lane</i>	4.5 m

COLUMN 1	COLUMN 2
(c) Maximum height:	
(i) <i>principal building</i>	9.0 m
(ii) <i>accessory building or structure</i>	5.0 m
(d) Maximum <i>parcel coverage</i>	30%
(e) Minimum horizontal dimension of a <i>single family dwelling</i> not including dimensions of an addition or a non-rectangular <i>building</i>	5.5 m

(5) Other Regulations

- (a) All persons carrying out a use permitted in the R-1 zone shall comply with the relevant provisions of Parts 1, 2 and 3 of Schedule A to this Bylaw.
- (b) No person shall use or permit the use of any portion of a *parcel* in the R-1 zone for:
 - (i) the *wrecking and repair of vehicles*; or
 - (ii) the storage of not more than one *derelict vehicle* in other than the *front yard*.

4.33 Community Commercial Zone: C-1

(1) Principal Uses

- (a) The following retail trades:
 - (i) convenience store, grocery store and pharmacy
 - (ii) liquor, beer and wine stores
 - (iii) shoe, apparel, fabric and yarn stores
 - (iv) household furniture, appliance and furnishing store
 - (v) book and music stores
 - (vi) ski shop, sporting goods and bicycle stores
 - (vii) toy, gift, novelty and souvenir stores
 - (viii) art gallery, artist and craft supply stores
 - (ix) florist, lawn and garden stores
 - (x) jewelry, electronics, camera stores
 - (xi) pet store
 - (xii) hardware and home goods store
- (b) Dry cleaning and laundry
- (c) Business and professional office
- (d) Medical and dental clinic
- (e) *Child care facility*
- (f) Miniature golf
- (g) Theatre and cinema
- (h) School and art studio for art, music, theatre and dancing
- (i) Beauty and barber shop
- (j) Fitness centre, racquet club, health spa
- (k) Food service
- (l) Tavern, bar, night club and pub
- (m) *Hotel*
- (n) *Motel*
- (o) Billiard hall, bowling alley, dance hall and amusement arcade
- (p) Bus depot
- (q) Funeral home
- (r) *Service club* or lodge
- (s) Publishing and print industry
- (t) Greenhouse and nursery product
- (u) Post office
- (v) *Government services*
- (w) Tourist information facility

(2) Accessory Uses

- (a) *Dwelling unit*
- (b) *Uses, buildings, and structures accessory to a permitted use*

(3) Parcel Area

In the C-1 zone no *parcel* shall be created unless it meets or exceeds the minimum *parcel* area based on provided level of servicing and if applicable, proposed permitted use as identified in section 2.2 of Schedule A to this Bylaw.

(4) Regulations

In the C-1 zone, subject to Section 2.2. of this Bylaw, no *building* or *structure* may be constructed or placed which contravenes the regulations contained in the table below. Column 1 identifies the matter to be regulated. Column 2 establishes the regulations.

COLUMN 1	COLUMN 2
(a) Maximum density:	
▪ Maximum number of <i>principal buildings</i>	one
▪ Maximum number of accessory <i>dwelling units</i> per <i>parcel</i>	one
(b) Minimum <i>setbacks</i> :	
<i>Building or structures</i> from:	
▪ <i>front parcel line</i>	4.5 m
▪ <i>rear parcel line</i> abutting a <i>highway</i> other than a <i>lane</i>	4.5 m
▪ <i>rear parcel line</i> abutting a <i>parcel</i> in a Residential (R) zone, Small Holdings (SH) zone, Resort (RES) zone or P-1 zone	6.0 m
▪ <i>side parcel line</i> on one side where a <i>parcel</i> is not serviced by a <i>lane</i>	5.0 m
▪ <i>side parcel line</i> abutting a <i>highway</i> other than a <i>lane</i> , a <i>parcel</i> in a Residential (R) zone, Small Holdings (SH) zone, Resort (R) zone or P-1 zone	6.0 m
(b) Maximum height:	
▪ <i>principal building</i>	12.0 m or 3 <i>storeys</i> whichever is less
▪ <i>accessory building or structure</i>	5.0 m or 1 <i>storey</i> whichever is less
▪ <i>detached dwelling unit accessory to a hotel or motel,</i>	9.0 m
(c) Minimum horizontal dimension of a <i>dwelling unit</i> , not including dimensions of an addition or a non-rectangular building	5.5 m

(5) Other Regulations

- (a) All persons carrying out a use permitted in the C-1 zone shall comply with the relevant provisions of Parts 1, 2 and 3 of Schedule A to this Bylaw.
- (b) No person shall use or permit the use of any portion of a *parcel* in the C-1 zone for:
- (i) the *wrecking and repair of vehicles*; or
 - (ii) the storage of not more than one *derelict vehicle* in other than the *front yard*.
- (c) All persons carrying out a use permitted in the C-1 zone shall comply with the relevant provisions of section 1.14 of Schedule A to this Bylaw with respect to *screening* and *outdoor storage*.
- (d) Where an accessory *dwelling unit* is proposed, it shall:
- (i) be designed and constructed as an integral part of the *principal building*;
 - (ii) be self-contained;

- (iii) have an entrance provided from outside the *building*, separate from that of any commercial use; and
 - (iv) be located above the *first storey* of the *building* or behind the commercial component of the *building*.
- (e) All persons carrying out a use permitted in the C-1 zone shall conduct the business or undertaking within a completely enclosed *building* except for:
 - (i) *off-street parking* and *loading spaces* and driveways;
 - (ii) *outdoor storage*, provided the storage yards are screened in accordance with the provisions of section 1.14 of Schedule A to this Bylaw;
 - (iii) display, rental and sales area;
 - (iv) outdoor seating *accessory to* food service.
- (f) Despite section 4.33 (4)(a), the maximum number of *principal buildings* for *motel* use shall not be restricted.
- (g) The provisions of section 4.33 (5)(d) shall not apply to a *dwelling unit accessory to a hotel or motel* use.

4.34 Service Commercial Zone: C-2**(1) Principal Uses****(a) The following retail uses:**

- (i) automobile dealer
- (ii) *recreational vehicle* dealer
- (iii) boat sales and service
- (iv) utility and horse trailer
- (v) gasoline service station
- (vi) automobile parts and accessory store
- (vii) motor *vehicle* repair shop
- (viii) car wash
- (ix) *manufactured home* dealer
- (x) automobile and truck rental and leasing services
- (xi) convenience store, provided the retail floor area does not exceed 150 m²
- (xii) ski shop, sporting goods and bicycle shop
- (xiii) art gallery, artist and craft supply stores
- (xiv) gift, novelty and souvenir shop
- (xv) antique shop
- (xvi) log home sales
- (xvii) small engine repair
- (xviii) feed and tack store
- (xix) household furniture, appliance and furnishing store
- (xx) shoe, apparel, fabric and yarn store

(b) The following accommodation uses:

- (i) *hotel*
- (ii) *motel*
- (iii) food service

(c) Billiard hall, bowling alley**(d) Simulated golf or miniature golf****(e) *Amusement park*****(f) Go cart track****(g) Drive-in theatre****(h) Bus depot****(i) Bottle collection depot****(j) Tourist information facility****(k) Dry cleaning and laundry****(l) *Veterinary clinic*****(m) *Government services*****(n) Exercise and fitness facility****(o) *Mini storage facility*****(2) Accessory Uses****(a) *Dwelling unit*****(b) Beauty and barber shop****(c) Tavern, bar, night club, and pub****(d) *Kennel accessory to a veterinary clinic***

- (e) Boat storage accessory to a boat sale and service or mini storage facility
- (f) Recreational vehicle storage accessory to mini storage facility
- (g) Other uses, buildings, and structures accessory to a permitted use

(3) Parcel Area

In the C-2 zone no *parcel* shall be created unless it meets or exceeds the minimum *parcel* area based on provided level of servicing and if applicable, proposed permitted use as identified in section 2.2 of Schedule A to this Bylaw.

(4) Regulations

In the C-2 zone, no *building* or *structure* may be constructed or placed which contravenes the regulations contained in the table below. Column 1 identifies the matter to be regulated. Column 2 establishes the regulations.

COLUMN 1	COLUMN 2
(a) Maximum density:	
▪ maximum number of <i>dwelling units</i>	one
(b) Minimum setbacks:	
(i) <i>Building</i> or <i>structures</i> from:	
▪ <i>front parcel line</i>	7.5 m
▪ <i>rear parcel line</i>	4.5 m
▪ <i>rear parcel line</i> abutting a <i>parcel</i> in a Residential (R) zone, Small Holdings (SH) zone, Resort (RES) zone or P-1 zone	6.0 m
▪ <i>side parcel line</i> on one side where a <i>parcel</i> is not serviced by a <i>lane</i>	5.0 m
▪ <i>side parcel line</i> abutting a <i>highway</i> other than a <i>lane</i> , a <i>parcel</i> in a Residential (R) zone, Small Holdings (SH) zone, Resort (RES) zone or P-1 zone	6.0 m
(ii) Gasoline pump, pump island, or above ground storage tank from <i>front parcel line</i>	10.0 m
(iii) Go cart track from an existing <i>dwelling unit</i> not on the same <i>parcel</i>	100 m
(c) Maximum height:	
▪ <i>principal building</i> or <i>structure</i>	12.0 m or 3 storeys whichever is less
▪ <i>accessory building</i> or <i>structure</i>	5.0 m or 1 storey whichever is less
▪ detached <i>dwelling unit</i> accessory to a <i>hotel</i> or <i>motel</i>	9.0 m
(e) Minimum horizontal dimension of a <i>dwelling unit</i> , not including dimensions of an addition or a non-rectangular <i>building</i>	5.5 m

(5) Other Regulations

- (a) All persons carrying out a use permitted in the C-2 zone shall comply with the relevant provisions of Parts 1, 2 and 3 of Schedule A to this Bylaw.
- (b) All persons carrying out a use permitted in the C-2 zone shall comply with the relevant provisions of section 1.14 of Schedule A to this Bylaw with respect to *screening* and *outdoor storage*.
- (c) All persons carrying out a use permitted in the C-2 zone shall conduct the business or undertaking within a completely enclosed *building* except for:

- (i) *off-street parking and loading spaces and driveways;*
 - (ii) *display, rental and sales areas;*
 - (iii) *amusement and recreation services; and*
 - (iv) *storage yards.*
- (d) Where a *dwelling unit* is proposed, it shall:
- (i) *be designed and constructed as an integral part of the principal building;*
 - (ii) *be self-contained;*
 - (iii) *have an entrance provided from outside the building, separate from that of any commercial use; and*
 - (iv) *be located above the first storey of the building or behind the commercial component of the building.*
- (e) The provisions of section 4.34 (5)(d) shall not apply to a *dwelling unit accessory* to a *hotel* or *motel* use.
- (f) Section 4.34 (4)(e) does not apply to *manufactured home* dealers or to a *dwelling unit accessory to manufactured home* dealers
- (g) No manufacturing of log homes shall be conducted in the C-2 zone.
- (h) Where a parcel utilized for *mini storage facility* abuts a Residential (R) or Small Holdings (SH) zone, *screening* shall be constructed along the *parcel lines* abutting the *parcels* in the Residential (R) zone or Small Holdings (SH) zone.
- (i) Boat and *recreational vehicle* storage *accessory to a mini storage facility* must be located within a three sided covered *structure*.

4.38 Public Institutional Zone: P-1

(1) Principal Uses

- (a) *School*, college and university
- (b) Church and *rural retreat* including counselling services and facilities
- (c) *Group home*
- (d) *Group day care*
- (e) Community hall, *service club* and lodge
- (f) *Rest home*
- (g) Senior citizen centre
- (h) Hospitals and diagnostic centre
- (i) Library
- (j) *Government services*
- (k) Cemetery

(2) Accessory Uses

- (a) *Dwelling unit*
- (b) Uses, *buildings*, and *structures accessory to* a permitted use

(3) Regulations

In the P-1 zone, no *building* or *structure* may be constructed or placed which contravenes the regulation contained in the table below. Column 1 identifies the matter to be regulated. Column 2 establishes the regulations.

COLUMN 1	COLUMN 2
(a) Maximum density: ▪ <i>dwelling unit</i>	one
(b) Minimum <i>setbacks</i> : (i) <i>Principal building</i> from: ▪ <i>front parcel line</i> ▪ <i>rear parcel line</i> ▪ <i>side parcel line</i> (ii) <i>Accessory building</i> or <i>structure</i> from: ▪ <i>front parcel line</i> ▪ <i>rear parcel line</i> ▪ <i>rear parcel line</i> adjacent to a <i>highway</i> other than a <i>lane</i> ▪ <i>side parcel line</i> ▪ <i>side parcel line</i> adjacent to a <i>highway</i> other than a <i>lane</i>	7.5 m 4.5 m 4.5 m 7.5 m 1.5 m 4.5 m 1.5 m 4.5 m
(c) Maximum height: ▪ <i>principal building</i> ▪ <i>accessory building</i> or <i>structure</i> ▪ <i>accessory dwelling unit</i> detached from a permitted use ▪ <i>manufactured home</i>	12.0 m 5.0 m 9.0 m 5.0 m

(4) Other Regulations

- (a) All persons carrying out a use permitted in the P-1 zone shall comply with the relevant provisions of Parts 1, 2 and 3 of Schedule A to this Bylaw.
- (b) No person shall use or permit the use of any portion of a *parcel* in the P-1 zone for:
 - (i) the *wrecking and repair of vehicles*; or
 - (ii) the storage of not more than one *derelict vehicle* in other than the *front yard*.

Appendix F

**Columbia Valley Child Care Snapshot
City Spaces Consulting
November 2022**

COLUMBIA VALLEY CHILD CARE SNAPSHOT

Eva Joseph Learning and Cultural Society,
Little Badgers Early Learning Programs

November 2022



Table of Contents

Purpose of this Report.....	1
Community Demographics.....	2
Existing Conditions and Space Inventory.....	3
Child Care Coverage Rates	4
Space Creation Targets	5
Future Child Care Spaces Needed	6
Conclusion	7



Purpose of this Report

The Eva Joseph Learning and Cultural Society and Little Badgers Early Learning Centre, with funding from the Columbia Basin Trust, commissioned this study to provide a snapshot of the current state of child care for the Columbia Valley region.

The contents of the study can assist with child care decision-making and determining appropriate assistance regarding staffing and funding to support the child care sector. Affordable, accessible, safe, and inclusive child care is an integral element of healthy, sustainable communities. Quality child care provides an environment that fosters foundational skill-building necessary for early childhood development, including social, educational, and emotional competencies.

Although this report provides a foundational understanding of child care needs, further research is necessary to gain a more robust understanding of the child care need, root causes of the current lack of child care spaces, and strategies to rectify the challenges presently observed in the community. Further engagement with child care providers, employers, educational establishments, and local families is recommended to better realize the need for child care spaces for underserved populations and further refine child care targets per age group.



Community Demographics

For this study, a compilation of Census subdivisions was used to capture key demographic indicators, encompassing the communities of Windermere, Invermere, Radium Hot Springs, Canal Flats, East Kootenay Electoral Area G, Shuswap IRI, and Columbia Lake IRI (the “Columbia Valley”), in alignment with the Windermere Health Area pictured in Figure 1.

In 2021, the total population of the Columbia Valley was 11,701 people. Approximately 11% of the population (1,345) are children aged 0 to 12 years. This figure is shared with the province, where 11% of BC’s total population is children aged 0 to 12 years.

In the Columbia Valley, there are 3,510 families, 375 of which are lone-parent families (in 75% of lone-parent families, the parent identifies as a woman). For most of the Columbia Valley population, English is the primary language spoken. French is the next most spoken language (3% of the population) and 7% of the population speaks non-official languages including German, Balto-Slavic languages, and Tagalog. Approximately 895 people in the Columbia Valley indicated an Indigenous identity, and 1,185 have self-identified as immigrants. Within the Columbia Valley, 945 households are considered low-income, 530 of which are in core housing need.

Of the total labour force commuting to work, the vast majority (87%) rely on a personal vehicle, while the remainder (13%) use alternative modes of transportation such as public transit, walking, or cycling to get to their place of employment.



Figure 1: Study Boundaries – Columbia Valley



Existing Conditions and Space Inventory

In conjunction with data from the East Kootenay Child Care Research and Referral Centre, a child care inventory list was prepared to determine the number of spaces presently offered in the community, as presented in Table 1 below.

Table 1: Child Care Providers and Licensed Spaces

Community	Program Name	Provider Type	Infant/Toddler (0-3)	Pre-School (3-5)	After School (6-12)	Total
Invermere	Beddies Babies Family Childcare	Independent	3	4	–	7
Akisqnuk	Little Badgers	Organization	8	20	20	48
Invermere	Little Tots	Independent	3	4	1	8
Wilmer	Playhouse Daycare	Independent	3	4	–	7
Invermere	Sonshine Children's Centre	Organization	20	19	–	39
Invermere	Windermere Valley Child Care Society	Organization	12	24	24	60
Invermere	Dragonfly Discovery Centre	Organization	24	12	20	56
Edgewater	Footprint	Independent	3	4	1	8
Radium Hot Spring	Creative Cubs	Organization	3	7	–	10
Radium Hot Springs	Rural Roots Early Learning Centre	Independent	3	5	–	8
Total			82	103	66	251

As of November 2022, Mountain Ridge Academy (Windermere), Panorama Wee Wascals (Panorama), and Einstein's Tree House (Edgewater) programs were closed due to lack of staffing, resulting in a net loss of 47 licensed child care spaces in the community. These facilities were therefore not included in the summary list in Table 1. Future child care centres in the Columbia Valley are projected to open their doors in 2023, although this information is not



included in this snapshot due to uncertainty around timing of opening and number of licensed spaces that may be available.

A lack of staff was a common theme discovered throughout the engagement period – child care providers indicated that a lack of qualified staff is one of the primary deficits in providing quality, licensed child care in the community. Other factors observed by operators that contribute to low retention rates include low wages for child care workers – including a lack of benefits, long hours, and mental / emotional burnout experienced in the sector. Although a lack of qualified staff has caused several providers to close their doors, many operators still have waitlists of 100+ children.

Child Care Coverage Rates

The child care coverage rate is a percentage based on the number of licensed child care spaces available for every 100 children in a community. Currently in the Columbia Valley, there are 251 child care spaces resulting in a coverage rate of 19%. To put this into context, a child care desert¹ is considered when the coverage rate is below 33%, qualifying the Columbia Valley as a child care desert. With the low coverage rate observed, it is apparent the child care needs of the Columbia Valley region are not being met.

Table 2 below demonstrates the current Columbia Valley region child population, available child care spaces, and child care coverage rates. It is apparent that the number of spaces for 6 to 12 year olds in particular is underserving the needs of the community, with only 66 spaces available for 755 children, representing a coverage rate of only 9%.

Table 2: Current Child Care Coverage Rates

Age Group	Number of Children	Child Care Spaces	Current Coverage Rate
0 to 3 years	275	82	30%
3 to 5 years	315	103	33%
6 to 12 years	755	66	9%
Total	1,345	251	19%

Source: Statistics Canada, Census of Population, 2021 (Age in Single Years Data)

¹ The Canadian Centre for Policy Alternatives (CCPA) 2018 report, Child Care Deserts in Canada



As a result of low availability, many families are without child care or with uncertainty around meeting their child care needs. This uncertainty may cause a ripple effect that could lead to parents having to modify work schedules, creating challenges with performing daily tasks and participating in the community, and, for some, leaving the community to find the child care services needed.

Space Creation Targets

Child care space creation targets are the number of child care spaces required to adequately address the needs of families. The methodology used to determine the Columbia Valley space creation targets, while an estimate only, is informed by other child care studies including the Surrey Child Care Gap Assessment (2011), Comox Valley Child Care Action Plan (2019), Township of Langley Child Care Action Plan (2020), and discussions with the East Kootenay Child Care Resource and Referral Program Coordinator. Based on these sources, the target coverage rates used in this analysis are 80% for children 0 to 3 years old, 70% for children 3 to 5 years old, and 55% for children 6 to 12 years.

To meet these target coverage rates, an additional 606 child care spaces are needed in the Columbia Valley – 138 spaces for children under 3 years, 118 spaces for children 3 to 5 years, and 350 spaces for children 6 to 12 years, as indicated in Table 3 below.

Table 3: Current Child Care Space Creation Targets, 2022

Age Group	Number of Children	Target Coverage Rate	Target Child Care Spaces	New Spaces Required to Meet Target
0 to 3 years	275	80%	220	138
3 to 5 years	315	70%	221	118
6 to 12 years	755	55%	416	350
Total	1,345		857	606



Future Child Care Spaces Needed

Table 4 below shows the number of child care spaces needed to meet the target coverage rates for each age group in 5- and 10-year increments.

The population of the Columbia Valley is projected to decrease slightly (–0.76%), and therefore targets reflect slightly reduced spaces over the 10-year period. The 2026 and 2031 projections use the Windermere Health Area statistics (in alignment with the subject geography illustrated in Figure 1) and have been adjusted slightly to match 2021 Census of Population baseline figures.

Table 4: Future Child Care Space Targets

Year	Future Number of Children	Future Target Child Care Spaces	Existing Child Care Spaces	New Spaces Required to Meet Future Target
Age Group 0 – 3				
2026	236	189	82	107
2031	235	188		106
Age Group 3 – 5				
2026	316	222	103	119
2031	302	212		109
Age Group 6 – 12				
2026	699	385	66	319
2031	642	354		288

Source: BC Stats Population Projections 2022

Although the Columbia Valley population is projected to decrease slightly, the space creation targets still demonstrate a significant need for more child care spaces in all age groups in the region.



Conclusion

There is presently only a 19% child care coverage rate observed in the Columbia Valley – categorizing the community as a child care desert. It is recommended to consider increasing the coverage rate in the community to 80% for ages 0 to 3 years, 70% for ages 3 to 5 years, and 55% for ages 6 to 12 to adequately service the community's child care needs.

In order to meet these targets, an increase of 606 child care spaces (for a total of 857 licensed spaces) is needed – an additional 138 spaces for under age 3 years, 118 spaces for ages 3 to 5 years and 350 spaces for ages 6 to 12 years.


As the population is not projected to increase over the next 10 years, it is not anticipated that the targets will increase significantly at this time. However, the targets should be re-evaluated as the community changes. It would be beneficial to engage with families to discover some of the nuances that families experience when accessing child care in the community.

As part of future strategies to address the need for more child care, it will be imperative to consider ways to create inclusive child care that can meet the diverse needs of the local population. Future considerations such as language, culture, and creating flexible options that can accommodate families with varying needs (e.g. parents with schedules that do not align with a typical 9 – 5 work day, lone parent families that may be working more than one job, etc.) should be explored in further detail when creating more child care spaces in the community.



Appendix G

Site Plan – Vermillion Property – Option 1 & 2



This drawing and all design information contained herein is copyright Haworth Development Consulting Ltd. Use of this drawing for other than the project specified is prohibited.
This drawing may not be reproduced in any form without prior written permission from Haworth Development Consulting.

REVISIONS		
REV	DATE	DESCRIPTION

**EDGEWATER
COMMUNITY HUB**

SCALE	AS NOTED
DATE	6 FEBRUARY 2024
ISSUED FOR	CLIENT REVIEW
PROJECT NUMBER	12285
DESIGN BY	RH
DRAWN BY	RH

DRAWING TITLE
SITE LOCATION

This drawing and all design information contained herein is copyright Haworth Development Consulting Ltd. Use of this drawing for other than the project specified is prohibited.
This drawing may not be reproduced in any form without prior written permission from Haworth Development Consulting.

REVISIONS

REV	DATE	DESCRIPTION

**EDGEWATER
COMMUNITY HUB**


SCALE	AS NOTED
DATE	6 FEBRUARY 2024
ISSUED FOR	CLIENT REVIEW
PROJECT NUMBER	12285
DESIGN BY	RH
DRAWN BY	RH

DRAWING TITLE
**COMMUNITY HUB
AREA EXISTING
CONDITIONS**

DRAWING NUMBER



All dimensions in metres.



This drawing and all design information contained herein is
copyright Haworth Development Consulting Ltd. Use of this drawing
for other than the project specified is prohibited.
This drawing may not be reproduced in any form without prior
written permission from Haworth Development Consulting.


REVISIONS		
REV#	DATE	DESCRIPTION

**EDGEWATER
COMMUNITY HUB**

SCALE	AS NOTED
DATE	6 FEBRUARY 2024
ISSUED FOR	CLIENT REVIEW
PROJECT NUMBER	12285
DESIGN BY	RH
DRAWN BY	RH

DRAWING TITLE
**DETAIL
LOTS 15 - 17
BLOCK 7
PLAN NEP1185**

DRAWING NUMBER



All dimensions in metres.



This drawing and all design information contained herein is
copyright Haworth Development Consulting Ltd. Use of this drawing
for other than the project specified is prohibited.

This drawing may not be reproduced in any form without prior
written permission from Haworth Development Consulting.

REVISIONS


REV#	DATE/REV	DESCRIPTION

**EDGEWATER
COMMUNITY HUB**

SCALE	AS NOTED
DATE	6 FEBRUARY 2024
ISSUED FOR	CLIENT REVIEW
PROJECT NUMBER	12285
DESIGN BY	RH
DRAWN BY	RH

DRAWING TITLE
**DETAIL
LOTS 15 - 17
BLOCK 7
PLAN NEP1185**

DRAWING NUMBER



All dimensions in metres.



This drawing and all design information contained herein is copyright Haworth Development Consulting Ltd. Use of this drawing for other than the project specified is prohibited.
This drawing may not be reproduced in any form without prior written permission from Haworth Development Consulting.

REVISIONS


REV#	DATE	DESCRIPTION

**EDGEWATER
COMMUNITY HUB**

SCALE	AS NOTED
DATE	6 FEBRUARY 2024
ISSUED FOR	CLIENT REVIEW
PROJECT NUMBER	12285
DESIGN BY	RH
DRAWN BY	RH

DRAWING TITLE
**DETAIL
LOTS 15 - 17
BLOCK 7
PLAN NEP1185**

DRAWING NUMBER



All dimensions in metres.



This drawing and all design information contained herein is copyright Haworth Development Consulting Ltd. Use of this drawing for other than the project specified is prohibited.
This drawing may not be reproduced in any form without prior written permission from Haworth Development Consulting.

REVISIONS


REV#	DATE	DESCRIPTION

**EDGEWATER
COMMUNITY HUB**

SCALE	AS NOTED
DATE	6 FEBRUARY 2024
ISSUED FOR	CLIENT REVIEW
PROJECT NUMBER	12285
DESIGN BY	RH
DRAWN BY	RH

DRAWING TITLE
**DETAIL
LOTS 15 - 17
BLOCK 7
PLAN NEP1185**

DRAWING NUMBER




All dimensions in metres.



Appendix H

Site Plan – Post Office Property



This drawing and all design information contained herein is copyright Haworth Development Consulting Ltd. Use of this drawing for other than the project specified is prohibited.

This drawing may not be reproduced in any form without prior written permission from Haworth Development Consulting.

REVISIONS		
REV	DATE	DESCRIPTION

**EDGEWATER
COMMUNITY HUB**

SCALE	AS NOTED
DATE	6 FEBRUARY 2024
ISSUED FOR	CLIENT REVIEW
PROJECT NUMBER	12285
DESIGN BY	RH
DRAWN BY	RH

DRAWING TITLE
SITE LOCATION

This drawing and all design information contained herein is copyright Haworth Development Consulting Ltd. Use of this drawing for other than the project specified is prohibited.
This drawing may not be reproduced in any form without prior written permission from Haworth Development Consulting.

REVISIONS		
REV	DATE	DESCRIPTION

**EDGEWATER
COMMUNITY HUB**

SCALE	AS NOTED
DATE	6 FEBRUARY 2024
ISSUED FOR	CLIENT REVIEW
PROJECT NUMBER	12285
DESIGN BY	RH
DRAWN BY	RH

DRAWING TITLE
**COMMUNITY HUB
AREA EXISTING
CONDITIONS**

DRAWING NUMBER



All dimensions in metres.



This drawing and all design information contained herein is
copyright Haworth Development Consulting Ltd. Use of this drawing
for other than the project specified is prohibited.
This drawing may not be reproduced in any form without prior
written permission from Haworth Development Consulting.


REVISIONS		
REV#	DATE	DESCRIPTION

**EDGEWATER
COMMUNITY HUB**

SCALE	AS NOTED
DATE	6 FEBRUARY 2024
ISSUED FOR	CLIENT REVIEW
PROJECT NUMBER	12285
DESIGN BY	RH
DRAWN BY	RH

DRAWING TITLE
**DETAIL
LOTS 14 - 17
BLOCK 2
PLAN NEP1185**

DRAWING NUMBER



This drawing and all design information contained herein is copyright Haworth Development Consulting Ltd. Use of this drawing for other than the project specified is prohibited.

This drawing may not be reproduced in any form without prior written permission from Haworth Development Consulting.

REVISIONS

REV	DATE	DESCRIPTION

EDGEWATER
COMMUNITY HUB

SCALE	AS NOTED
DATE	6 FEBRUARY 2024
ISSUED FOR	CLIENT REVIEW
PROJECT NUMBER	12285
DESIGN BY	RH
DRAWN BY	RH

DRAWING TITLE
**DETAIL
LOTS 14 - 17
BLOCK 2
PLAN NEP1185**

DRAWING NUMBER

This drawing and all design information contained herein is
copyright Haworth Development Consulting Ltd. Use of this drawing
for other than the project specified is prohibited.
This drawing may not be reproduced in any form without prior
written permission from Haworth Development Consulting.

REVISIONS


REV	DATE	DESCRIPTION

**EDGEWATER
COMMUNITY HUB**

SCALE	AS NOTED
DATE	6 FEBRUARY 2024
ISSUED FOR	CLIENT REVIEW
PROJECT NUMBER	12285
DESIGN BY	RH
DRAWN BY	RH

DRAWING TITLE
**DETAIL
LOTS 14 - 17
BLOCK 2
PLAN NEP1185**

DRAWING NUMBER



This drawing and all design information contained herein is
copyright Haworth Development Consulting Ltd. Use of this drawing
for other than the project specified is prohibited.

This drawing may not be reproduced in any form without prior
written permission from Haworth Development Consulting.

REVISIONS



REV#	DATE	DESCRIPTION

**EDGEWATER
COMMUNITY HUB**

SCALE	AS NOTED
DATE	6 FEBRUARY 2024
ISSUED FOR	CLIENT REVIEW
PROJECT NUMBER	12285
DESIGN BY	RH
DRAWN BY	RH

DRAWING TITLE
**DETAIL
LOTS 14 - 17
BLOCK 2
PLAN NEP1185**

DRAWING NUMBER



All dimensions in metres.

